

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: VESS OIL CORPORATION  
Address: 1700 Waterfront Parkway, Bldg. 500 Wichita, KS 67206  
Phone: (316) 682-1537 Operator License #: 5030  
Type of Well: oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 10/28/08 (Date)  
by: Duane Krueger (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Lansing Depth to Top: 1668 Bottom: 1675 T.D. \_\_\_\_\_  
Kansas City Depth to Top: 1960 Bottom: 2006 T.D. 2050  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

30159-00-00  
API Number: 15-015-96648  
Lease Name: Paulson A  
Well Number: 91  
Spot Location (QQQQ): \_\_\_\_\_ - NW - SW - NE  
Feet from 1980 3334 North /  South Section Line  
1980 2092 East /  West Section Line  
Sec. 2 Twp. 26 S. R. 4  East  West  
County: Butler  
Date Well Completed: 11/19/65  
Plugging Commenced: 10/28/08  
Plugging Completed: 10/28/08

KCC  
PET  
PERCOPS

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Lansing	sw, sli. oil	1868	1875	8-5/8"	217	none
Kansas City	sw, sli oil	1960	2006	5-1/2"	2047	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run tubing to 1650'. Circulate mud out of well. Mix and pump 40 sx Class A; 3% cc, spot it. Pull tubing out. Wait 2 hours  
Wireline tag cement at 1310'. Perf 4 holes at 270'. Establish circ. Mix and pump 126 cmt sx Class A,  
circ. cement. Hole standing full inside and outside. Consolidated Ticket #19009

Name of Plugging Contractor: Simmons Well Service, Inc. License #: 32991  
Address: 6730 SE Satchell Creek Road, Leon, KS 67074

RECEIVED  
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: Vess Oil Corporation  
State of Kansas County, Sedgwick, ss.  
Casey Coats (Employee of Operator) or (Operator) on above-described well, being first duly

OCT 31 2008

CONSERVATION DIVISION  
WICHITA, KS


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Casey Coats  
(Address) 1700 Waterfront Parkway, Bldg. 500, Wichita, KS 67206

SUBSCRIBED and SWORN TO before me this 29th day of October

Michelle D. Henning  
Notary Public

My Commission Expires: \_\_\_\_\_



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten initials/signature