

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warroir inc.

Address: P.o. Box 399 Garden City Ks. 67846

Phone: (620) 272-1023 Operator License #: 4058

Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 10/27/08 (Date)

by: Pat staab (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Arbuckle Depth to Top: 334' Bottom: BA T.D. 3347'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-07408-00-00

Lease Name: Finger

Well Number: #1

Spot Location (QQQQ): C - SW - NE - NE

4290' Feet from North / South Section Line

990' Feet from East / West Section Line

Sec. 33 Twp. 16 S. R. 12 East West

County: Barton

Date Well Completed: 9/21/57

Plugging Commenced: 10/27/08

Plugging Completed: 10/27/08

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 31 2008
CONSERVATION DIVISION
WICHITA, KS

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface Conductor & Production) | | | | |
|---------------------------|---------|--|-------|------|--------|------------|
| Formation | Content | From | To | Size | Put In | Pulled Out |
| Arbuckle | oil | surface | 312' | 85/8 | 312' | 0 |
| | | surface | 3336' | 51/2 | 3336' | 0 |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf 1450', 800' and 300' 2spf. Ran tbg to 2808'. Swift hooked up to tbg, mixed and pumped 150sx cement w/ 300# of hulls. Pulled tbg to 1800'.

Swift hooked up to tbg, Mixed and pumped 140sx cement w/ 200# of hulls. Cement circulated to surface. Pulled tbg.

Swift hooked up to 51/2 casing, Mixed and pumped 40sx cement, pressured to 350# shut in. Swift hooked up to 85/8, mixed and pumped 20sx

Cement. Pressured to 250# shut in. All cement was 60/40 pos, 4% gel. Cut casing off and back filled

Name of Plugging Contractor: expresswell service & supply inc License #: 32382 6426 KCC PRT
per CP2/3

Address: P.O. Box 466 Nesscity Ks. 67560


Name of Party Responsible for Plugging Fees: American Warrior Inc.

State of Kansas County, Finney, ss.

Jody Smith (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 399 Garden City Ks. 67846



SUBSCRIBED and SWORN TO before me this 28 day of October, 20 08

[Signature] My Commission Expires: 09-12-09
Notary Public