

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-179-20656-00-00

LEASE NAME Ziegler

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1-A

660 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 17 TWP. 10S RGE. 28 (X) or (W)

COUNTY Sheridan

LEASE OPERATOR Coastal Oil & Gas Corporation

ADDRESS One Leadership Sq., Ste. 1700, Okla. City, OK 73102

PHONE# (405) 239-7031 OPERATORS LICENSE NO. 6593

Date Well Completed 10/30/82

Character of Well Oil

Plugging Commenced 4/16/86

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4/16/86

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District 6, Hays, Kansas

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Lansing/Kansas City Depth to Top: 4014 Bottom 4028 T.D. 4562

Show depth and thickness of all water, oil and gas formations..

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|---------------------|---------|------|------|-------|--------|------------|
| Lansing/Kansas City | Oil | 4014 | 4028 | 4 1/2 | 4156 | 6' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pumped 145 sx. 65/35/2 Poz + 3 sx. Hulls from 0-3732'. Pressure to 1000 PSI. Pumped 303 sx. 65/35/2 Poz in to 8 5/8 x 4 1/2 annulus. Pressure to 1000 PSI. Cut off 8 5/8 & 4 1/2" csg 6' BGL. Witnessed by Carl Goodrow of KCC.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementers License No. N/A

Address 24 S. Lincoln, Russell, KS 67665

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Coastal Oil & Gas Corporation (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Douglas T. Chumley

(Address) One Leadership Square, Suite 1700
Oklahoma City, OK 73102

SUBSCRIBED AND SWORN TO before me this 1st day of May, 19 86

Laurie Parker
Notary Public


My Commission Expires: 1-14-87

RECEIVED
STATE CORPORATION COMMISSION

MAY 05 1986

CONSERVATION DIVISION
Wichita, Kansas

05-05-1986



DUAL INDUCTION SFL LOG W GR



15-179-20656-0000

COMPANY: CINCO EXPLORATION LIMITED

WELL: ZIGLER A #1

Ⓟ 4014-28

FIELD: WILDCAT

COUNTY: SHERIDAN

STATE: KANSAS

NATION: USA

LOCATION: 660' FSL & 1980' FWL

SEC: SE SW 17

TWP: 10S

RGE: 28W

PERMANENT DATUM: GROUND LEVEL ELEVATIONS-

ELEV. OF PERM. DATUM: 2724.0 ' KB: 2729.0 ' DF: 2727.0 ' GL: 2724.0 '

LOG MEASURED FROM: KB

5.0 ' ABOVE PERM. DATUM

DRLG. MEASURED FROM: KELLY BUSHING

DATE: OCT 17, 1982
RUN NO: 1

DEPTH-DRILLER: 4562.0 '
 DEPTH-LOGGER: 4558.0 '
 BTM. LOG INTERVAL: 4552.0 '
 TOP LOG INTERVAL: 270.0 '

CASING-DRILLER: 290 '
 CASING-LOGGER: 287 '
 CASING: 8 5 8
 WEIGHT: 20.00 LB/F
 BIT SIZE: 7 7 8
 DEPTH: 290 ' 4562 '

RECEIVED
STATE CORPORATION COMMISSION

MAR 13 1985
03-13-1985
CONSERVATION DIVISION
Wichita, Kansas