

15-179-00022-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Sheridan County, Sec. 21 Twp. 10S Rge. 28W (E) (W)

Location as "NE/CNW/SW" or footage from lines. NW NW NW

Lease Owner Anschutz Drilling Company, Inc.

Lease Name Rupp Well No. 1

Office Address 709 Union Nat'l Bk Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-24 19 52

Application for plugging filed 9-24 19 52

Application for plugging approved 9-24 19 52

Plugging commenced 9-24 19 52

Plugging completed 9-24 19 52

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 4560 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	222'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Top plug set at 40' with 10 sacks cement
Bottom plug set 210' with 15 sacks cement

FILED
SEP 30 1952
CONSERVATION DIVISION
Wichita, Kansas


Name of Plugging Contractor Anschutz Drilling Company, Inc.
Address 709 Union Nat'l Bk Bldg., Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Leon C. Mehler (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leon C. Mehler
709 Union Nat'l Bk Bldg., Wichita, Ks.
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of September, 1952
My commission expires May 2, 1956
Jacqueline Hanna Notary Public.

24-2675-S 2-52-20M
PLUGGING
FILE SEC 21 T 10 R 282
BOOK PAGE 12 LINE 45



DRILLER'S LOG

Anschutz Drilling Company, Inc.
and
Pack Oil Company, Inc.
#1 Rupp
NW NW NW - 21-10S-28W
Sheridan County, Kansas

<u>FROM</u>	<u>TO</u>		
0	85	Surface clay	COMMENCED: 9-8-52
85	115	Sand	COMPLETED: 9-24-52
115	278	Shale	
278	480	Shale & shells	<u>CASING RECORD</u>
480	1085	Shale, sand & shells	Set 8-5/8" surface casing at
1085	1550	Shale & sand	222 feet with 150 sacks
1550	1800	Shale, shells & pyrite	cement.
1800	1845	Shale & shells	
1845	1870	Anhydrite	ELEVATION: 2742 RB
1870	2045	Shale, shells & red bed	
2045	2303	Shale & red bed	<u>TOPS</u>
2303	2333	Anhydrite	Howard 3608
2333	2710	Shale & shells	Topeka 3637
2710	3854	Lime & shale	Heebner 3831
3854	4112	Lime	Toronto 3851
4112	4445	Lime & shale	Lansing 3863
4445	4450	Lime	Base/Kansas City 4115
4450	4466	Lime, chert & shale	First Marmaton Lime 4148
4466	4543	Lime & shale	Pennsylvania Conglomerate 4312
4543	4560	Lime & shale	Mississippi 4430
	4560	TOTAL DEPTH	
		D&A	

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #1 Rupp, located NW NW NW of Section 21-10S-28W, Sheridan County, Kansas.

ANSCHUTZ DRILLING COMPANY, INC.

BY: *Leon L. Mehler*
Leon L. Mehler

Subscribed and sworn to before me this 29th day of September, 1952.

Jaqueline Hinnan
Notary Public

My Commission Expires: May 2, 1956



RECEIVED
CORPORATION COMMISSION

SEP 30 1952
09-30-1052W
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC-21-10S-28W
BOOK PAGE 17 LINE 45