


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Sheridan County. Sec. 1 Twp. 10S Rge. (E) 29 (W)
Location as "NE/CNW&SW&S" or footage from lines C NW/4 NE/4
Lease Owner Abercrombie Drilling, Inc.
Lease Name HEIER Well No. 1
Office Address 801 Union Center; Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 3, 19 68
Application for plugging filed (Verbally) April 3, 19 68
Application for plugging approved (Verbally) April 3, 19 68
Plugging commenced April 3, 19 68
Plugging completed April 3, 19 68
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Nichols
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4235 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7-5/8"	226'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug @1240' w/80 sx., 2nd plug @240' w/15 sx., and top plug at 40' w/10 sx. Job was completed at 5:00 p.m., 4-3-68.

RECEIVED
STATE CORPORATION COMMISSION
APR 8 1968
CONSERVATION DIVISION
Wichita, Kansas
04-08-1968

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor ABERCROMBIE DRILLING, INC.
Address 801 Union Center; Wichita, Kansas


STATE OF Kansas COUNTY OF Sedgwick, ss.
A. L. Abercrombie (employee or owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
801 Union Center; Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of April, 19 68
Mildred Saxton
Mildred Saxton Notary Public.

My commission expires October 5, 1968



15-179-20086-00-00

CONTRACTOR'S WELL LOG

OWNER: Abercrombie Drilling, Inc.
 FARM NAME: HEIER #1
 LOCATION: C NW/4 NE/4, Sec. 1-10S-29W
 Sheridan County, Kansas
 SPUD DATE: March 25, 1968
 COMPLETION DATE: April 3, 1968

0	189	Clay & Sand Streaks
189	200	Sand & Gravel
200	895	Shale
895	1800	Shale & Sand
1800	2075	Shale w/Sand Streaks
2075	2203	Sand
2203	2240	Red Bed Shale
2240	2875	Shale
2875	3215	Shale & Lime
3215	3485	Lime & Shale
3485	3655	Shale & Lime
3655	4005	Lime & Shale
4005	4235	Lime
	4235	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 APR 8 1968
 CONSERVATION DIVISION
 Wichita, Kansas

04-08-1968

Drill 227' of 11" surface hole and set 7-5/8" casing @226' w/125 sx. cement.
 Cement circulated. Plug was down 5:00 p.m., March 25, 1968.
 Dry and Abandoned.

ELECTRIC LOG TOPS:

ELEVATION:

Anhydrite	2424	(+ 407)	2831 K. B.
Howard	3612	(+ 781)	2829 D. F.
Topeka	3701	(- 870)	2823 G. L.
Heebner	3920	(-1089)	
Toronto	3950	(-1119)	
Lansing	3958	(-1127)	
Base/Kansas City	4204	(-1373)	
E.L.T.D.	4236	(-1405)	

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

A. L. Abercrombie, Abercrombie Drilling, Inc., does hereby certify that the above and foregoing is a true and correct copy of the log of the #1 HEIER, C NW/4 NE/4, Section 1-10S-29W, Sheridan County, Kansas, as reflected by the files of Abercrombie Drilling, Inc. as of the 5th day of April, 1968.

A. L. Abercrombie
 A. L. Abercrombie

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas.

Mildred Saxton
 Mildred Saxton
 Notary Public

My Commission Expires:

October 5, 1968

