

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19138-00-00
Spot: NWNE Sec/Twnshp/Rge: 5-14S-15W
4620 feet from S Section Line, 1980 feet from E Section Line
Lease Name: MERMIS B Well #: 6
County: RUSSELL Total Vertical Depth: 3314 feet

Operator License No.: 31428
Op Name: CRAWFORD, JEFF DBA LONESTAR OIL
Address: PO BOX 417
VICTORIA, KS 67671

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| CIBP | | 2826 | | |
| PROD | 5.5 | 3314 | 0 | 250 SX |
| SURF | 8.625 | 237 | 0 | 150 SX |

107.71

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/27/2008 8:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JEFF CRAWFORD Company: LONESTAR OIL COMPANY Phone: (785) 735-2725

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls.
Lok-set at 2826'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/27/2008 11:00 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2000' - pumped 70 sxs cement.
Pulled tubing to 1000' - pumped 100 sxs cement - cement circulated.
Pulled tubing out of well - filled casing with 25 sxs.
Hooked up to braden head - pumped 25 sxs cement. Max. P.S.I. 250#.
Hooked onto casing and squeezed. Max. P.S.I. 200#.
No hulls pumped.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3146 | 3152 | | |
| 3138 | 3142 | | |
| 3124 | 3128 | | |
| 3092 | 3108 | | |
| 3078 | 3084 | | |
| 3054 | 3064 | | |

RECEIVED
KANSAS CORPORATION COMMISSION
NOV 03 2008
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKET #33271.

Plugged through: TBG

INVOICED
DATE 11-10-08
INV. NO. 2009060712

District: 04

Signed Ray A. Dinkel PIRT
(TECHNICIAN)

CM

OCT 29 2008

PKT