

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-20547-00-00  
Spot: SESESW Sec/Twnshp/Rge: 23-14S-11W  
330 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: HINES Well #: 4  
County: RUSSELL Total Vertical Depth: 2920 feet

Operator License No.: 9408  
Op Name: TRANS PACIFIC OIL CORPORATION  
Address: 100 S MAIN STE 200  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2915	0	100 SX
SURF	8.625	280	0	94.90

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/14/2008 9:30 AM  
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.  
Proposal Rcvd. from: GARY SHARP Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 1/4# flocele - 2 sxs C.C. - 400# hulls

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/14/2008 3:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran 2 3/8" tubing to 420' - could not get back 627'.  
Mixed 150 sxs cement - cement circulated out the braden head and backside.  
Pulled tubing out of the well - hooked up to 4 1/2" casing - pumped cement until good cement circulated out of braden head.  
Shut braden head off - pumped cement down casing.  
Had 150 to 200# of pressure - broke down - went on vacuum, mixed more cement and hulls.  
Shut down and waited on cement.  
Mixed all the cement with 150# hulls. Shut in with a little vacuum.  
10/15/2008 - checked full.  
1:00 P.M. - 10/15/2008 - Frank and Ken with Trans Pacific witnessed cement down approximately 160'. Frank will call when they top off the well.  
Left approximately 2200' of 2 3/8" tubing in the well.

Perfs:

Top	Bot	Thru	Comments
2854	2859		

**INVOICED**  
DATE 11-10-08  
INV. NO. 2009060717

RECEIVED  
KANSAS CORPORATION COMMISSION  
NOV 03 2008  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY-TICKEET #322915.

Plugged through: TBG

District: 04

Signed

R. ADKEL

(TECHNICIAN)

CM

Form CP-2/3

OCT 17 2008

PKT

SALINE BASIN PET. CO.

#4 HINES

23-14-11W  
SE SE SW


119 S, SANTA FE, SALINA, KS.  
CONTR SHIELDS DRG.

CTY RUSSELL

GEOL DICK FOLEY

FIELD WILSON CREEK

K 1680 KB CM 6/27/72 <sup>CARD</sup> ISSUED 8/3/72 IP P 21 BOPD + TR WTR  
LANS 2854-59



API 15-167-20,547

SMP	TOPS	DEPTH	DATUM
SC		520	+1160
GR HAV		2106	-426
TOP		2429	-749
WIL CR TOP		2465	-785
HFEB		2722	-1042
BN LM		2814	-1134
LANS		2833	-1153
RTD		2920	-1240

8 5/8" 280; 4 1/2" 2915/100sx

DST(1) 2459-2480/1', 15'DM W/OIL SP,  
BHP 74-62#, FP NA

DST(2) 2848-2870/1', 65'OCM, 5'FO, BHP  
256-162#, FP NA

MICT, PF (LANS) 20/2854-59, A300 MCA +  
2000 RET 15% + 2000 15% REG, SWB AC &  
SWB 15 BOPH 6% WTR, POP.

NO LOG

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS