

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-21105-00-00
Spot: SWSNW Sec/Twnshp/Rge: 3-10S-29W
3100 feet from S Section Line, 3710 feet from E Section Line
Lease/Unit Name: KRANNAWITTER Well Number: A-2
County: SHERIDAN Total Vertical Depth: 4309 feet

Operator License No.: 31900
Op Name: NOR-WEST KANSAS OIL, L.L.C.
Address: RR 2, BOX 14
WAKEENEY, KS 67672

Conductor Pipe: Size _____ feet: # 140.04
Surface Casing: Size 8.625 feet: 219
Production: Size _____ feet:
Liner: Size _____ feet:

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/27/2001 2:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: BILL WYNN Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Order 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 02/27/2001 4:00 AM KCC Agent: HERB DEINES

Actual Plugging Report:

1st. Plug at 2470' w/25 sxs. Anhydrite 2435' - 2470'.
2nd. Plug at 1550' w/100 sxs. Dakota 1230' - 1530'.
3rd. Plug at 275' w/40 sxs. Surface pipe to 219'.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

INVOICED
DATE 03-15-2001
INV. NO. 2001061507

RECEIVED
STATE CORPORATION COMMISSION
03-15-2001
MAR 15 2001

CONSERVATION DIVISION
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY

Plugged through: DP

District: 04

Signed _____

(TECHNICIAN)