

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

KCC PCT CPSD
NU
4307 4290

API Well Number: 15-101-21057-00-00
Spot: SEENW Sec/Twnshp/Rge: 15-17S-29W
4307 ~~4290~~ feet from S Section Line, ~~2970~~ feet from E Section Line
Lease Name: SNIDER 3095 Well #: 2-15
County: LANE Total Vertical Depth: 4650 feet

Operator License No.: 31142
Op Name: PETROLEUM PROPERTY SERVICES, IN
Address: 125 N MARKET SUITE 1251
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1119		WITH 260 SX CMT
PROD	4.5	4625	0	WITH 200 SX CMT <i>151.13</i>
SURF	8.625	338		WITH 190 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/07/2008 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: LEON KUHN Company: PETROLEUM PROPERTY SERVICE Phone: (785) 483-1559

Proposed Plugging Method: MIX 300#HULLS & 25 SX CMT THEN 40 BBL GEL WATER THEN CMT TO SURFACE. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF NEEDED.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/08/2008 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

TIED ONTO CASING AND PUMPED 300# HULLS, 25 SX CMT, 15 SX GEL, THEN 145 SX CMT. WELL WAS STILL ON VACUUM. SHOT FL. CMT WAS DOWN ABOUT 1400'. 10/8/08: TIED ONTO CASING AND PUMPED 90 SX CMT. PRESSURED TO 500#. RELEASED PRESSURE AND CASING STAYED FULL. TIED ONTO BACKSIDE & PRESSURE RIGHT UP.

Perfs:

Top	Bot	Thru	Comments
4537	4540		
4450	4454		
4322	4325		
4305	4308		
4254	4259		
4193	4196		
4168	4171		
4132	4136		
3990	3993		

INVOICED
DATE 11-13-08
INV. NO. 2009060731
RECEIVED
KANSAS CORPORATION COMMISSION


Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

NOV 05 2008

Plugged through: CSG

CONSERVATION DIVISION
WICHITA, KS

District: 01



Signed Michael Maier
(TECHNICIAN)

PCT
Form CP-23