

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-19197-00-01
Spot: SWSWSE Sec/Twnshp/Rge: 16-11S-16W
351 feet from S Section Line, 2421 feet from E Section Line
Lease Name: LUNDY Well #: 5
County: ELLIS Total Vertical Depth: 3405 feet

Operator License No.: 5252
Op Name: NIXON, R P OPERATIONS, INC
Address: 207 W 12TH
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3403	0	450 SX
SURF	8.625	280	0	175 SX

110.666

Well Type: EOR UIC Docket No: E13535.2 Date/Time to Plug: 10/30/2008 9:00 AM
Plug Co. License No.: 5252 Plug Co. Name: NIXON, R P OPERATIONS, INC
Proposal Rcvd. from: DUANE ACHTERBERG Company: NIXON, R P OPERATIONS, INC Phone: (785) 656-0038

Proposed Plugging Method: Ordered 235 sxs 60/40 pozmix - 4% gel - 500# hulls - 7 sxs gel spacers.
Last MIT passed 04/13/2006.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/30/2008 11:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls, followed with 7 sxs gel spacer with 200# hulls and 120 sxs cement.
Max. P.S.I. 350#. S.I.P. 350#.
Hooked on backside - instant pressure 500#.

Perfs:

Top	Bot	Thru	Comments
3154	3156		
3093	3095		
3042	3044		
2969	2971		

INVOICED
DATE 11-13-08
INV. NO. 2009060735

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 04 2008

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Richard Williams
(TECHNICIAN)

CM

Form CP-2/3

NOV 03 2008

PPT

replacament card

R P NIXON OPERATIONS
HAYS KS 67601

16-11 -16W
SW SW SE

#5 LUNDY OWWW

site: 3 N & 3-1/2 W OF FAIRPORT KS
contr: JAY-LAN CORP
genl: DAN NIXON

city: ELLIS
field: LUEB EAST

API 15-051-01075

fr date	07/12/89	spd date	07/27/89	drig comp	07/28/89	card issued	10/04/89	last revised	06/14/93
---------	----------	----------	----------	-----------	----------	-------------	----------	--------------	----------

ELV: 1788 KB, 1783 GL LOG
tops.....depth/datum
*ANH280 +1508
TOP2705 -017
HEEB2945 -1157
TOR2968 -1180
LANS2995 -1207
BKC3238 -1450
*CONG3302 -1514
*ARB3353 -1565
LTD3309 -1521
RTD OLD3404 -1616
*SAMPLE TOP

IP status:
 INJ, LKC 3042-3188 OA,
 INFO RELEASED: 6/14/93 - WAS DELAYED COMP
 OLD INFO: OPERATOR WAS E H RIGGS, 1 FINCH, SPD
 05/13/58 , 05/26/58 8-5/8" 280, D&A, ARB , 05/26/58
 (CARD ISSUED 05/30/58)
 CONTR: PRIME DRILLING
 NOTE: DID NOT LOG BELOW 3309' DUE TO INSERT
 FLOAT NOT HOLDING VERY GOOD ON 4-1/2" CMT JOB
 NO CORES
 ALTERNATE SAMPLE TOPS: HEEB 2942 (-1154), TOR
 2965 (1177), LANS 2993 (-1205)

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

R P NIXON OPERATIONS
HAYS KS 67601

16-11 -16W
SW SW SE

#5 LUNDY OWWW

- DST (1) 3023-3057 (LKC), / OP 60", REC 60' MSW, FP NA ISIP 940#
- DST (2) 3142-3187 (LKC), / OP 60", REC 10' M, FP NA ISIP 30#
- DST (3) 3357-3361 (ARB), / OP 60", REC 345' SLJ OIL & GCSW, FP NA ISIP 1110#
- DST (4) 3361-3369 (ARB, W/STR PKR), / OP 60", REC 1830' SW, FP NA ISIP 1070#

NEW INFO: FR 07/12/89 , RE-ENTERED 07/27/89 WSH DWN DC 07/28/89 CSG: SET 4-1/2"
 3403 / 450 SX MICT - CO, PF (LKC) 3154-3158, 3093-3095, 3042-3045, AC 2000 GAL (15%),
 SWB DWN, WIW - INJECTION RATE SATISFACTORY, 1/31/90