

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-30159-00-00
Spot: NWSWNE Sec/Twnshp/Rge: 2-26S-4E
3334 feet from S Section Line, 2092 feet from E Section Line
Lease Name: PAULSON A Well #: 91
County: BUTLER Total Vertical Depth: 2050 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2047		110 SX
SURF	8.625	217		90 SX

66.63

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/28/2008 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: _____ Phone: (316) 655-1997

Proposed Plugging Method:

35 SXS @ 1660', CIRCULATE FROM 270' TO SURFACE W/ 60/40 POZMIX 4% GEL

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 10/28/2008 3:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TUBING @ 1,650', CONSOLIDATED MIXED & PUMPED 40 SXS CLASS A 3% CC AND DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 1,310'. TESTED CASING @ 200#, HELD OK. SHOT SQUEEZE HOLES @ 270'. SWEDGED INTO 5-1/2" CASING, CONSOLIDATED MIXED & PUMPED 126 SXS CLASS A CEMENT TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 3:00 PM. 10/28/2008.

Perfs:

Top	Bot	Thru	Comments
1985	2006		
1971	1979		
1960	1964		KC
1668	1675		LANSING

INVOICED

DATE: 11-18-08
INV. NO. 2009060754

Remarks: CONSOLIDATED CEMENT TICKET #19009

Plugged through: TBG

District: 02

Signed

Duane Krueger
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 13 2008

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

PKT