

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-055-20375-00-01

Spot: NESW

Sec/Twnshp/Rge: 5-21S-30W

2012 feet from S Section Line, 2096 feet from W Section Line

Lease Name: I M INCORPORATED

Well #: 1

County: FINNEY

Total Vertical Depth: 4954 feet

Operator License No.: 30742

Op Name: PALOMINO PETROLEUM, INC.

Address: 4924 SE 84TH ST  
NEWTON, KS 67114

String Size Depth (ft) Pulled (ft) Comments

PC 2112 WITH 235 SX CMT

PROD 5.5 4704 0 WITH 200 SX CMT

SURF 8.625 401 WITH 200 SX CMT

161.01

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 10/27/2008 2:30 PM

Plug Co. License No.: 31151

Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: JOHN SCHOOLCRAFT

Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 200# HULLS & 20 SX CMT. MUD SPACER TO 2150' THEN 20 SX CMT. MUD SPACER TO 1300' THEN 20 SX CMT. MUD SPACER TO 400' THEN 50 SX CMT TO SURFACE. CHECK BACKSIDE

Plugging Proposal Received By: KEN JEHLIK

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 10/27/2008 6:00 PM

KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 200# HULLS & 20 SX CMT ON BOTTOM AT 4264'. 1ST PLUG MUD SPACER TO 2150' THEN 20 SX CMT AT 2150'. 2ND PLUG MUD SPACER TO 1300' THEN 20 SX CMT AT 1300'. 3RD PLUG MUD SPACER TO 400' THEN 35 SX CMT AT 400-0'. PRESSURED TO 1300#. HELD AT 1000#. HOOK TO 5 1/2" X 8 5/8" ANNULUS & PUMPED 15 SX CMT TO 250#. HELD.

Perfs:

Top	Bot	Thru	Comments
4402	4408		
4262	4264		

RECEIVED  
KANSAS CORPORATION COMMISSION

NOV 12 2008

CONSERVATION DIVISION  
WICHITA, KS

INVOICED


Remarks: USED COMMON CEMENT BY SARGENTS.

DATE 11-18-08

Plugged through: CSG

INV. NO. 2009060747

District: 01



Signed

*[Signature]*

(TECHNICIAN)

Form CP 2/3

*[Signature]*  
PKT