

321 R 00-01

3-28-89  
API NUMBER 15-

179-20,374A

6 031230

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C NW SE, SEC. 15, T 10 S, R 30 W&E  
1980 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3567 Lease Name Hecht Well # 1 OWWO

Operator: Totten Res. Inc. County Sheridan 148.53

Name & Address 2506 Green Leaf Court  
Wichita, Ks. 67226

Total Depth 4570 feet

Inducer Pipe: Size \_\_\_\_\_ feet  
Casing: Size 8 5/8 feet 298

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated OWWO

Plugging Contractor AlliedCement Co. License Number \_\_\_\_\_

Address Russell, Ks.

Company to plug at: Hour: AM Day: 28 Month: Mar Year: 19 89

Plugging proposal received from Dean Ives

(company name) Totten Res. Inc. (phone) \_\_\_\_\_

Were: 8 5/8" set at 298' cwc 5 1/2" set at 4328' w/150 sks. Packer shoe . PBD  
4283'. Perfs 4176' - 4215'. Perf 2440' Anhy. 1500' Kiowa SH. From log.  
Order 350 sks 65/35 Poz 10% Gel. 2% Dicol 500# Hulls. Allied Cement Co.  
Joe Newman Water Trucks. L.K. Wireline.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:45PM Day: 28 Month: Mar Year: 19 89

ACTUAL PLUGGING REPORT Squeeze 5 1/2" casing w/250 sks cement blend w/500# Hulls  
mixed into max psi 1000#. Close in psi. 300#. Squeeze 8 5/8" w/100sks to max psi  
200# Close in psi 200# . Plug complete.

Remarks: Anhy 2440' 2480'.  
(If additional description is necessary, use BACK of this form.)

I ~~XXXX~~ did not observe this plugging.

INVOICED

Signed Carl Goodrow (TECHNICIAN)  
Carl Goodrow

DATE 4-20-89

INV. NO. 24405 3-28 MAY 16 1989 JUN 12 1989