

6 070902

3-2

184 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 179 - 20,993 - 00 - 00

SW SW NE, SEC. 15, T 10 S, R 30 WEX
2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3007

Lease Name Ruby Albers Well # 1

Operator: Western Ks. Exp

County Sheridan 148.00

Name & Address Box 126

Well Total Depth 4554 feet

Hays, Ks. 67601

Conductor Pipe: Size feet

Stan Younger

Surface Casing: Size 8 5/8 feet 212

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Western Ks. Drilling License Number 4083

Address Hays, Ks. 67601

Company to plug at: Hour: AM Day: 2 Month: Mar Year: 19 91

Plugging proposal received from Dwight French

(company name) Western Ks. Drilling (phone)

were: 8 5/8 212 ft. s.p. cwc w/140 sks 60/40 poz 2% gel 3% cc. By Halco L.K.C. well.

No arb. Elev. 2893. Anhy 2456. Mud 43 vis 9.3 lbs. 12 w.l.

Proposal 190 sk,s 60/40 poz 6% gel 3% cal cl. Spot and displace cement through drill pipe; circulate; spot mud between all plugs. 1 25 sks at 2460.

2. 100 sks w/ 1 sk f.c. at 1540; 3 40 sks at 260 ft. 4. 10sks at 40 ft. 15 sks in rathole (circ).

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 2:00PM Day: 2 Month: Mar Year: 19 91

ACTUAL PLUGGING REPORT Western Ks. ordered 190 sks 60/40 poz 6% gel 35 cal cl.

Spotted cement through drill stem (circulated) Mud between all plugs.

1st plug at 2460 w/25 sks cement

2nd plug at 1540 w/100 sks cement w/1 sk f.c.

3rd plug at 260 w/40 sks cement

4th plug at 40 w/10 sks cement.

RECEIVED
STATE CORPORATION COMMISSION
03-22-1991
MAR 22 1991

Remarks: 15 sks in rathole (cir) by Halliburton Cement
(If additional description is necessary, use BACK of this form.)

INVOICED (If you did not observe this plugging.)

DATE 4-3-91

INV. NO. 31323

lib.S.

Signed Marion J. Schmidt (TECHNICIAN)

Marion J. Schmidt