

7-18 264 R  
API NUMBER 15- 179-21,015-00-00

6 070932

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW SE SW, SEC. 19, T 10 S, R 30 WE  
990 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3372

Lease Name Ferguson Well # 1

Operator: Morrison-Dixon Oil Operations, Inc.  
Name & Address 155 N. Market, Suite #950  
Wichita, Kansas 67202

County Sheridan 148.85  
Well Total Depth 4580 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 262'

\* Micheal W. Dixon

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling Company License Number

Address 801 Union Center, Wichita, Kansas 67202

Company to plug at: Hour: A.M. Day: 18th Month: July Year: 19 91

Plugging proposal received from Harold Maley

(company name) Abercrombie Drilling Inc. (phone) 316-264-9632

were: 8 5/8" 262' S.P. cir. w/190 sx. 60/40 Pozmix - 3% C.C. - 2% Gel. (By Allied Cmt.)

Miss. Well - Elv. 2897' - Anhy. 2456' - Mud condition 46 vis. - 8.9 weight - W.L. 10.4.

Proposal 190 sx. 60/40 Pozmix - 6% Gel. - 3% C.C. - Spot with drill stem, circulated hole, heavy mud between all plugs. 25 sx. @ 2460' - 100 sx. w/1 sx. F.C. @ 1545' - 40 sx. @ 300' - 10 sx. @ 40' - 15 sx. in rathole (circulate).

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10:30P.M. Day: 18th Month: July Year: 19 91

ACTUAL PLUGGING REPORT Morrison-Dixon ordered 190 sx. 60/40 Posmix - 6% Gel. - 3% C.C. and

1 sx. Flocele - circulated hole, spotted with drill stem - heavy mud between all plugs.

1st plug @ 2460' w/25 sx. cmt. 4th plug @ 40' w/10 sx. cmt.

2nd plug @ 1545' w/100 sx. cmt. w/1 sx. F.C. 15 sx. in rathole (circulate)

3rd plug @ 300' w/40 sx. cmt.

RECEIVED STATE CORPORATION COMMISSION

Remarks: Cemented by: Allied Cement.

JUL 30 1991 07-30-1991 CONSERVATION DIVISION Wichita, Kansas

INVOICED

(If additional description is necessary, use BACK of this form.)

DATE 8-12-91

INV. NO. 32685

Handwritten initials

Signed Marion J. Schmidt (TECHNICIAN)