

4 060092

6-19

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 193-20,519-00-00

NW NE NE , SEC. 5 , T 10 S, R 31 W/E  
4950 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3966

Lease Name Albers Well # 1

Operator: Wanker Oil Company

County Thomas 149.66

Name & Address Rt. 2 Box 14

Well Total Depth 4605 feet

WaKeeney, KS 67672

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 251

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XXXXXXXX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Emphasis Oil Operations License Number 8241

Address Russell, KS

Company to plug at: Hour: 4:00AM Day: 19 Month: June Year: 19 90

Plugging proposal received from Tom Alm

(company name) Emphasis Oil Operations (phone) 913-483-3518

were: Order 200 sxs. 60/40 pos 6%gel 1/4# floccel per sxs.  
Space all plugs with heavy drill mud through drill pipe.

Plugging Proposal Received by Herb Deines  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXXXX

Operations Completed: Hour: 4:00AM Day: 19 Month: June Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2600' with 25 sxs. Anhydrite 2586-2615'  
2nd plug at 1715' with 100 sxs. Dakota 1412-1712'  
3rd plug at 300' with 40 sxs. Surface pipe to 251'  
4th plug at 40' with 10 sxs.  
rathole with 15 sxs. mousehole with 10 sxs.

Remarks: Allied Cementing  
(if additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KANSAS  
DATE 06-23-1990  
INV. NO. 28530

Herb Deines

Signed [Signature]  
(TECHNICIAN)  
Herb Deines