

4

060034

11-23

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 193-20,489-00-00  
130 West of NE NW NE, SEC. 5, T 10 S, R 31 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

4950 feet from S section line  
1780 feet from E section line

Operator: Raymond Oil Company, Inc.  
Name & Address: P.O. Box 48788  
Wichita, KS 67202

Lease Name Albers "A" Well # 1  
County Thomas 151.78

Well Total Depth 4670 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 255

Abandoned Oil Well Gas Well Input Well SWD Well D&A XXXXXXXX

Other well as hereinafter indicated

Plugging Contractor Murfin Drlg Co. License Number 6033

Address Wichita, KS

Company to plug at: Hour: 2:30AM Day: 23 Month: November Year: 19 89

Plugging proposal received from Steve Carlton

(company name) Murfin Drlg Co. (phone) 316-267-3241

were: Space all plugs throughdrill pipe with heavy drilling mud.

Order 185 sxs. 60/40 pos 6%gel 1/4# flocel per sx.

Arbuckle not reached.

Plugging Proposal Received by Herb Deines (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None XXXXXXXXXXXX

Operations Completed: Hour: 2:30AM Day: 23 Month: November Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2600' with 20 sxs. Anhydrite 2581-2611'

2nd plug at 1715' with 100 sxs. Dakota 1411-1711'

3rd plug at 305' with 40 sxs. Surface pipe to 255

4th plug at 40' with 10 sxs. wiper plug at 40'

rathole with 15 sxs.

Remarks: B-J Titan

(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 12-7-89

INV. NO. 26693

11-23

J.S.

Signed Herb Deines (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION WEL 1 1989 12-11-1989 CONSERVATION DIVISION Wichita, Kansas