

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-179-21,015-00-00

LEASE NAME Ferguson

WELL NUMBER #1

990' Ft. from S Section Line

3630' Ft. from E Section Line

SEC. 19 TWP. 10S RGE. 30 (E) or (W)

COUNTY Sheridan

Date Well Completed \_\_\_\_\_

Plugging Commenced 7-18-91

Plugging Completed 7-18-91

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Morrison/Dixon Oil Operations, Inc.

ADDRESS 155 N. Market, Suite 950, Wichita, KS 67202

PHONE# (316) 264-9632 OPERATORS LICENSE NO. 3372

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-18-91 (date)

by Marion Schmidt (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? \_\_\_\_\_

Producing Formation L/KC-Miss. Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4580'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED  
STATE CORPORATION COMMISSION  
08-20-1991  
AUG 20 1991  
CON. DIVISION  
Wichita, Kansas

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	262'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Fill w/heavy mud; set 1st plug @ 2460'-2360' w/25 sx; 2nd plug @ 1545'-1145' w/100 sx; 3rd plug @ 30'-140' w/40 sx; 4th plug @ 40'-surface w/10 sx; rathole 15 sx; 190 sx 60-40 posmix 6% gel 1/4# Flocel per sx.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Morrison/Dixon Oil Operations, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801, Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 19th day of August, 19 91

Edagela Standard  
Notary Public

My Commission Expires: March 20, 1993