

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Russell Oil, Inc.
Address: PO Box 1469
Phone: 815)609-7000 Operator License #: 3293
Type of Well: D & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11-06-2008 (Date)
by: Bruce Basye (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-141-20,397-00-00
Lease Name: Sigle Trust
Well Number: 6
Spot Location (QQQQ): NW - NE - SE - NW
1,600 Feet from North / South Section Line
2,060 Feet from East / West Section Line
Sec. 2 Twp. 10 S. R. 12 East West
County: Osborne
Date Well Completed: 11-05-2008
Plugging Commenced: 11-06-2008
Plugging Completed: 11-06-2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	234'	Cmtd. w/160sax

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run drill pipe to 950', pump 25 sax cement thru drill pipe; run drill pipe to 760', pump 100 sax cement thru drill pipe; run drill pipe to 285', pump 40 sax cement thru drill pipe; push wiper plug to 40', dump 10 sax cement on plug to cellar. Circulate 30 sax cement down rat hole and 15 sax cement down mouse hole.

Name of Plugging Contractor: Shields Drilling Co. License #: 5184
Address: PO Box 709, Russell, KS 67665
Name of Party Responsible for Plugging Fees: Russell Oil, Inc.
State of KANSAS County, RUSSELL, ss.

Burton Beery, Drilling Supt. Contractor
(Employee of Shields Drilling Co.)
sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Burton Beery
(Address) PO Box 709, Russell, KS 67665

SUBSCRIBED and SWORN TO before me this 12th day of November, 2008

Ruth Phillips
Notary Public

My Commission Expires: 5-26-2011
RUTH PHILLIPS
State of Kansas

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

NOV 13 2008
CONSERVATION DIVISION
WICHITA, KS

KANSAS CORPORATION COMMISSION




Shields

Russell, Kansas

WELL LOG

Operator: Russell Oil, Inc.
 Well: Sigle Trust #6
 Commenced: 10-29-08
 Completed: 11-06-08
 Contractor: Shields Drilling Co.

Well Description: 1,600' FNL, 2,060' FWL
 NW/4 Sec. 2-10S-12W
 Osborne Co., KS



Elevation: 1,905' KB

Treatment:

Production: D & A

Tops:

CASING RECORD

Size	Run	Pulled
8 5/8"	234'	Cmtd. w/160 sax

..... Figures Indicate Bottom of Formations

Sand & shale	590'
Sand	675'
Sand & redbed	938'
Anhydrite	967'
Redbed & shale	1,600'
Shale	1,895'
Shale & lime	3,120'
Lime	3,240' RTD

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 13 2008

CONSERVATION DIVISION
WICHITA, KS

Notes