

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Schankie Well Service, Inc.
Address: 1006 SW Blvd, PO Box 397 Madison, KS 66860
Phone: (620) 437-2595 Operator License #: 6470
Type of Well: Oil Docket #:
The plugging proposal was approved on: 8-21-08 (Date)
by: Mike Heffern, Dist #3 (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Bartlesville Depth to Top: 1861' Bottom: 1884' T.D. 1884'

API Number: 15-111-19011-0D-00
Lease Name: Nuessen
Well Number: A6
Spot Location (OOQQ): NE - NW - NE -
4950 Feet from North / South Section Line
1650 Feet from East / West Section Line
Sec. 31 Twp. 21 S. R. 12 East West
County: Lyon
Date Well Completed: 4-22-57
Plugging Commenced: 8-21-08
Plugging Completed: 8-21-08

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Contains data for 8 5/8" and 4 1/2" casings.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Spot 15sk cement plug down 2 3/8" tubing @ 1800', Gel Spacer, Spot 10sk cement plug @ 800', Gel Spacer, Perforate @ 150', Spot 30sk cement plug @ 160' to surface


RECEIVED
NOV 17 2008

Name of Plugging Contractor: Schankie Well Service, Inc. License #: 6470
Address: 1006 SW Blvd, PO Box 397 Madison, KS 66860
Name of Party Responsible for Plugging Fees: Schankie Well Service, Inc., Madison, KS 66860
State of Kansas County, Greenwood, ss.

KCC WICHITA

Randall Schankie, Secretary (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Handwritten Signature]
(Address) PO Box 397 Madison, KS 66860



DESCRIBED and SWORN TO before me this 29th day of September 2008
Carol R. Bolen My Commission Expires: 1-9-2009
Notary Public

48-1214033
 Shop # 620 437-2661
 Cellular # 620 437-7582
 Office # 316 685-5908
 Office Fax # 316-685-5926
 Shop Address: 3613A Y Road
 Madison, KS 66860

Hurricane Services, Inc.
 P.O. Box 782228
 Wichita, KS 67278-2228

Cement, Acid or Tools
 Service Ticket
 02685

DATE 8-21-08

COUNTY Lyon CITY _____

CHARGE TO Schenkie Well Services
 ADDRESS P.O. Box 397 CITY Madison ST Ks ZIP 66860-0397
 LEASE & WELL NO. Muessen #6A CONTRACTOR CO. Tools
 KIND OF JOB Plug To Abandon SEC. 31 TWP. 21s RNG. 12E
 DIR. TO LOC. _____ OLD NEW

Quantity	MATERIAL USED	Serv. Charge	
			700.00
55 SKS	60/40 Poz mix cement		478.50
190 lbs	Gel 4%		38.00
300 lbs	Gel Spacers (between Plugs)		60.00
	BULK CHARGE		
M/L	BULK TRK. MILES		200.00
-	PUMP TRK. MILES (5 miles from shop)		M/L
4 1/2	Hrs. water Truck		360.00
	PLUGS		
		5.8% SALES TAX	33.44
		TOTAL	1869.94

T.D. _____ CSG. SET AT _____ VOLUME _____
 SIZE HOLE _____ TBG SET AT _____ VOLUME _____
 MAX. PRESS. _____ SIZE PIPE 4 1/2"
 PLUG DEPTH _____ PKER DEPTH _____
 PLUG USED _____ TIME FINISHED _____

RECEIVED
 NOV 17 2008

REMARKS: NOTE: Well had been squeezed a couple of times > Ref. casing at 150'
Plug through 2" Tubing > Spot 15 SKS at 1800'
10 SKS at 800'
30 SKS at 160' To Surface

KCC WICHITA

EQUIPMENT USED

NAME	UNIT NO.	NAME	UNIT NO.
<u>Kelly Kimbulin</u>	<u>185</u>	<u>Jerry #91, Clayton #193</u>	
<u>Brad Butler</u>		<u>Witnessed by Cliff Schenkie</u>	
HSI REP.		OWNER'S REP.	

Precision Well Perforators

PO Box 401
Chanute, KS 66720

Date 7/31/2008
Invoice # 2390

Bill To
Schankie Well Service
Box 397
Madison, KS 66860

Ship To

P.O. #
Terms Net 30

Ship Date 7/31/2008
Due Date 8/30/2008
Other

Item	Description	Qty	Price	Amount
Perforation	Nuessan #8A 07/31/2008			
	Perforate Well at 800.0'		450.00	450.00
Perforation	at 150.0'		200.00	200.00
	So Well can be properly plugged with cement			
Perforation	Nuessan #A-6 08/21/2008			
	Perforate Well at 150.0'		450.00	450.00
	So Well can be properly plugged with cement			

RECEIVED
NOV 17 2008
KCC WICHITA

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas


COPY

Company- WHITE & ELLIS PRODUCING, INCORPORATED
Farm- Nucssen "A" No. 6

SEC. 31 T. 21 R. 12E
NE NW NE

Total Depth. 1884'
Comm. 4-10-57 Comp. 4-22-57
Shot or Treated.

County Lyon KANSAS



Contractor. White & Ellis Drilling Company
Issued. 5-25-57

Elevation. ?

Production. 20 BOPD

CASING:

8 5/8" @126' w/75 sx cem.
4 1/2" @1872' w/50 sx cem.

Figures indicate Bottom of Formations.

Kelly bushing measurement 5' above ground level.

soil	8
lime	12
shale & shells	57
shale & lime strks	86
lime	917
shale & lime shells	126
shale & shells	150
shale & lime strks	165
lime	194
shale & shells	260
lime	300
shale & lime strks	432
lime	440
lime & shale strks	465
lime	471
shale & lime strks	542
lime	552
shale & shells	562
lime	591
lime & shale strks	622
shale & shells	880
Top of Douglas	
sand	940
lime	1127
gray shale & shells	1184
Top of Kansas City	
lime	1332
lime & shale	1336
lime	1349
lime & shale	1366
shale strks	1390
lime w/shale strks	1431
shale & shells	1475
shale, gray & shells	1484
lime & shale strks	1552
shale & lime shells	1572
lime & shale strks	1629
shale & shells	1685
sandy shale	1700
dark shale & shells	1725
shale & shells, sandy	1801
dark shale & shells	1870
Top of Bartlesville	
sand	1874
Cable Tools	
sand, free oil	1884
Total Depth	

SCOUT TOPS

Douglas	880
Lansing	940
Kansas City	1184

RECEIVED
NOV 17 2008
KCC WICHITA
K. G. S. LIBRARY

Nuessen Oil Co.

In account with Schankie Well Service, Inc. Squeeze and drill out
cement for repair of 4 1/2" casing in well #Nuessen A-6.

Both g Power Swivel & Rig @ \$120/hr

Rig = Walker-Neer Spudder @ \$60/hr

Jan. 1983

4hrs Rig	Run measuring line to 1388'. Make-up 4 1/2" tools.	
6hrs Rig	Drill with spudder on bridge at 1388' to 1754'.	
6hrs Rig	Bridge pipe to 1700' With chat. Consolidated pumped 4 1/2" plug to 1375'. Drove plug down to 1415' with tools. Upper plug stopped at 1333'.	
3hrs Both	Run tubing and drill collars. Drill out plug with swivel. No cement.	
3hrs Rig	Pulled tubing and collars.	
5hrs Rig	Pressure 4 1/2" casing to 280 psi, leak in casing. Finished laying down tubing.	
6hrs Rig	Consolidated pumped 4 1/2" plug to 652'. Drove plug down to 682' with tools. Upper plug stopped at 626'. Cement hole with 125 sacks. Used tank truck for water to cement with.	
5hrs Both	Run tubing & drill collars, Drill out cement & plug for 645'-738'.	
1hr Rig		
5hrs Both	Pressure 4 1/2" casing to 260 psi, casing held. Run tubing to 1700'.	
1hr Rig	Drill lower plug to 1730'.	
5hrs Both	Drill out lower plug to bottom of pipe at 1782' and lost circulation.	
6hrs Rig	Lay down tubing & collars. Drill out with spudder from 1872'-1884'.	
2hrs Rig	Bail on well.	
Total	move rig in and out	\$ 300.00
40hrs Rig	4 1/2" Tooth Bit	100.00
18hrs Both	Tubing Rental	200.00
	40hrs Rig	2,400.00
	18hrs Both	<u>2,160.00</u>
		\$5-160.00

RECEIVED
NOV 17 2008

PD 2/2/83 KCC WICHITA

NUESSEN OIL COMPANY

Route 1

Madison, Kansas 66860

Please Nuessen Oil Co.

For the month Dec. Cont.

Check No.	Date Paid	Description	Debit	Credit
1536	12/28/82	UNITED CEMENTING & ACID CO, INC.		
		Nuessen #A-6		
		1 Pump Truck		
		150 Sacs Common Cement @ 4.65	\$432.80	
		" " Bulk @ .80	697.50	
		Drayage (7.50 X .65 X 36)	120.00	
		36 miles on Pump Truck @ 1.90 per mile	175.50	
		2 4-1/2" Top Rubber Plugs @ 31.00	68.40	
			62.00	
		Tax	46.69	
			\$1,602.89	\$1,602.89
1537	12/28/82	CONSOLIDATED OIL WELL SERVICES		
		Nuessen #A-6: Ton Mileage-30	\$159.75	
		Pumping Charge - Cementing	\$421.50	
		150 Sacks Bulk Cement @ 4.90	735.00	
		2 4-1/2" Cementing Plug @ 20.00	40.00	
		Vacuum Truck 4-1/2 hrs. @ 44.00	198.00	
		Tax	31.00	
			\$1,585.25	\$1,585.25
1538	12/28/82	GEORGE NUESSEN		
		Pumping for the month 11/20/82 to 12/20/82	\$700.00	700.00
1539	12/28/82	LYNETTE NUESSEN		
		Bookkeeping for the month of December	\$25.00	25.00
		Received on account for Property Taxes:		
		George & Rita Nuessen	\$1,465.00	
		Leonarda Nuessen	1,465.00	
		Leo Schankie & Sons	1,465.00	
		Jo Ann Williams	1,465.00	
			\$5,860.00	\$5,860.00
*****			\$5,614.03	
George & Rita Nuessen	4/16	\$1,403.50		
Leonarda Nuessen	4/16	1,403.51		
Leo Schankie & Sons	4/16	1,403.51		
Jo Ann Williams	4/16	1,403.51		
		\$5,614.03		

pd. Jan. 20, 1983 ck# 6030

RECEIVED
NOV 17 2008
KCC WICHITA