

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Schankie Well Service, Inc.
Address: 1006 SW Blvd, PO Box 397 Madison, KS 66860
Phone: (620) 437-2595 Operator License #: 6470
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 8-25-08 (Date)
by: Mike Heffern, Dist #3 (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Bartlesville Depth to Top: 1873' Bottom: 1900' T.D. 1900'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-111-19010-00-00
Lease Name: Nuessen
Well Number: A5
Spot Location (QQQQ): C - NE - NE - NE
4950 Feet from North / South Section Line
660 Feet from East / West Section Line
Sec. 31 Twp. 21 S. R. 12 East West
County: Lyon
Date Well Completed: 1-25-57
Plugging Commenced: 8-25-08
Plugging Completed: 8-25-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	86'	None
				5 1/2"	1875'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


Spot 15sk cement plug down 2 3/8" tubing @ 1800', Gel Spacer, Perforate @ 800', Spot 15sk cement plug @ 800', Gel Spacer, Perforate @ 150', Spot 30sk cement plug @ 160' to surface

RECEIVED
NOV 17 2008

Name of Plugging Contractor: Schankie Well Service, Inc. License #: 6470
Address: 1006 SW Blvd, PO Box 397 Madison, KS 66860
Name of Party Responsible for Plugging Fees: Schankie Well Service, Inc. Madison, KS 66860
State of Kansas County, Greenwood, ss.

KCC WICHITA

Randall Schankie, Secretary (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Randall Schankie, Sec
(Address) PO Box 397, Madison, KS 66860

SUBSCRIBED and SWORN TO before me this 29th day of September, 2008
Carol R. Bolen My Commission Expires: 1-9-2009
Notary Public

Handwritten initials/signature

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
 508 East Murdock, Wichita, Kansas


COPY

SEC. 31 T. 21 R. 12E
 C NL NE NE

Company- WHITE & ELLIS
 Farm- Nuessen "A" No. 5

Total Depth. 1900'
 Comm. 12-26-56 Comp. 1-25-57
 Shot or Treated.
 Contractor. White & Ellis Drlg. Inc.
 Issued. 5-11-57

County Lyon
 KANSAS



Elevation. ??

Production. 25 BOPD

Figures Indicate Bottom of Formations.

soil	10
brkn lime	20
lime	28
shale	32
lime brkn	45
shale	70
lime brkn	83
shale-shells	165
lime	170
shale	280
shale-shells	360
shale-lime stks	532
lime	575
shale-lime stks	815
lime	823
sand-shale	865
lime-shale stks	880
sand	936
lime	1015
lime	1077
shale-lime stks	1185
lime	1206
lime-shale	1213
lime stks	1266
brwn sdy lime-no odor	1278
lime	1363
brwn sdy lime-no odor	1369
brwn lime-shale stks	1394
shale-shells	1498
lime	1508
lime w/shale stks	1534
shale-shells	1598
lime-shale stks	1603
shale-shells	1619
shale-lime stks	1665
shale sdy	1680
shale-shells	1700
shale-sand	1725
lime-shale stks	1805
sdv shale	1825
shale	1873
sand-odor, show of oil	1877
sand-odor, show of oil	1900
Total Depth	1900

TOPS:

Douglass Sec.	880
Lansing	1015
Kansas City	1185
Bartlesville	1873

K. G. S. LIBRARY

RECEIVED
 NOV 17 2008

KCC WICHITA

Hurricane Services, Inc.
P.O. Box 782228
Wichita, KS 67278-2228

Cement, Acid or Tools
Service Ticket

02707

ED:ID# 48-1214033
Shop # 620 437-2661
Cellular # 620 437-7582
Office # 316 685-5908
Office Fax # 316-685-5926
Shop Address: 3613A Y. Road
Madison, KS 66860

DATE 8-25-08

COUNTY Lyon CITY _____

CHARGE TO Schenk Well Services
ADDRESS P.O. Box 397 CITY Madison ST Ks. ZIP 66860-0397
LEASE & WELL NO. Nuesse #5-A CONTRACTOR CO. Tools
KIND OF JOB Plug To Abandon SEC. _____ TWP. _____ RNG. _____
DIR. TO LOC. _____ OLD NEW

Quantity	MATERIAL USED	Serv. Charge
		700.00
60 SKs	60/40 Poz mix cement	522.00
200 lbs	Gel 4%	40.00
300 lbs	Gel Spacer (between Plugs)	60.00
	BULK CHARGE	200.00
M/C	BULK TRK. MILES	M/C
-	PUMP TRK. MILES <u>5 miles from Shop</u>	320.00
4 Hrs	Water Truck #193	
	PLUGS	
		5.8% SALES TAX <u>39.19</u> <u>36.08</u>
		TOTAL <u>1881.19</u> <u>1878.08</u>

T.D. _____
SIZE HOLE 7 7/8"
MAX. PRESS. _____
PLUG DEPTH _____
PLUG USED _____

CSG. SET AT _____ VOLUME _____
TBG SET AT _____ VOLUME _____
SIZE PIPE 5 1/2"
PKER DEPTH _____
TIME FINISHED _____

REMARKS: Note: Shot Holes in casing at 800' and 150' - Taged at 1825'
Plug through 2" Tubing Spot 15 SKs at 1800'
15 SKs at 800'
30 SKs at 160' To Surface

RECEIVED
NOV 17 2008

KCC WICHITA

EQUIPMENT USED

NAME	UNIT NO.	NAME	UNIT NO.
<u>Kelly Kimberlin</u>	<u>#185</u>	<u>Jerry #186, Clayton #193</u>	
<u>Brad Butler</u>		<u>witnessed by Cliff Schenk</u>	
HSI REP.		OWNER'S REP.	

Precision Well Perforators
PO Box 401
Chanute, KS 66720

Date 8/25/2008
Invoice # 2428

Bill To
Schankie Well Service
Box 397
Madison, KS 66860

Ship To

P.O. #
Terms Net 30

Ship Date 8/25/2008
Due Date 9/24/2008
Other

Item	Description	Qty	Price	Amount
Shoot off Tubi...	Neussen #A-4 08/25/2008 Shoot off 2 3/8" Tubing at 1786.0'		450.00	450.00
Perforation	Neussen #A-5 08/25/2008 Perforate Well at 800.0'		450.00	450.00
Perforation	at 150.0' So Well can be properly plugged with cement		200.00	200.00
Perforation	Neussen #A-4 08/28/2008 Perforate Well at 800.0'		450.00	450.00
Perforation	at 150.0' So Well can be properly plugged with cement		200.00	200.00

RECEIVED
NOV 17 2008
KCC WICHITA

Thank You!

Precision Well Perforators
luden@arcplasma.com

Subtotal \$1,750.00
Sales Tax (0.0%) \$0.00
Total \$1,750.00
Payments/Credits \$0.00
Balance Due \$1,750.00