

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Schankie Well Service, Inc.

Address: 1006 SW Blvd, PO Box 397 Madison, KS 66860

Phone: (620) 437 2595 Operator License #: 6470

Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 8-28-08 (Date)

by: Mike Heffern, Dist#3 (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

Bartlesville Depth to Top: 1800' Bottom: 1840' T.D. 1840'

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-111-19009-00-00

Lease Name: Nuessen

Well Number: A4

Spot Location (QQQQ): NW - NE - NE -

4950 Feet from  North /  South Section Line

990 Feet from  East /  West Section Line

Sec. 31 Twp. 21 S. R. 12  East  West

County: Lyon

Date Well Completed: NA

Plugging Commenced: 8-28-08

Plugging Completed: 9-02-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				5 1/2"	1840'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Spot 15sk cement plug down 2 3/8" tubing @ 1740', Gel Spacer, Perforate @ 800', Spot 15sk cement plug @ 800', Gel Spacer, Perforate @ 150', Spot 38sk cement plug @ 160' to surface, Spot 27sk cement plug to surface

**RECEIVED**  
**NOV 17 2008**

Name of Plugging Contractor: Schankie Well Service, Inc. License #: 6470

Address: 1006 SW Blvd, PO Box 397 Madison, KS 66860

**KCC WICHITA**

Name of Party Responsible for Plugging Fees: Schankie Well Service, Inc. Madison, KS 66860

State of Kansas County, Greenwood, ss.

Randall Schankie, Secretary (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.


(Signature) Randall Schankie, Sec

(Address) PO Box 397 Madison, KS 66860

SUBSCRIBED and SWORN TO before me this 29<sup>th</sup> day of September, 2008

Carol R. Bolen My Commission Expires: 1-9-2009

Notary Public



*Handwritten initials*

FED ID#

4R-1014022

Hurricane Services, Inc.  
P.O. Box 782228  
Wichita, KS 67278-2228

Cement, Acid or Tools  
Service Ticket

02710

Shop # 620 437-2661  
Cellular # 620 437-7582  
Office # 316 685-5908  
Office Fax # 316-685-5926  
Shop Address: 3613A Y Road  
Madison, KS 66860

DATE 8-28-08

COUNTY Lyon CITY \_\_\_\_\_

CHARGE TO Schenkic Well Services

ADDRESS P.O. Box 397 CITY Madison ST Ks. ZIP 66860-0397

LEASE & WELL NO. Muessen # 4A CONTRACTOR CO. Tools

KIND OF JOB Plug To Abandon SEC. \_\_\_\_\_ TWP. \_\_\_\_\_ RNG. \_\_\_\_\_

DIR: TO LOC. \_\_\_\_\_ OLD NEW

Quantity	MATERIAL USED	Serv. Charge	
			700.00
68 sks	60/40 Pozmix cement		591.60
235 lbs	Gel 4%		47.00
300 lbs	Gel Spacer (between Plugs)		60.00
	BULK CHARGE		
M/c	BULK TRK. MILES		200.00
-	PUMP TRK. MILES <u>5 miles from Shop</u>		N/C
4 Hrs	Water Truck #193		320.00
	PLUGS		
		5.8% SALES TAX	40.52
		TOTAL	1959.12

T.D. \_\_\_\_\_

CSG. SET AT \_\_\_\_\_ VOLUME \_\_\_\_\_

SIZE HOLE 7 7/8"

TBG SET AT \_\_\_\_\_ VOLUME \_\_\_\_\_

MAX. PRESS. \_\_\_\_\_

SIZE PIPE 5 1/2"

PLUG DEPTH \_\_\_\_\_

PKER DEPTH \_\_\_\_\_

PLUG USED \_\_\_\_\_

TIME FINISHED \_\_\_\_\_

REMARKS: Note: Shot Holes in casing at 800' and 150'

RECEIVED

Plug Through 2" Tubing

Spot 15 sks. at 1740'

NOV 17 2008

15 sks at 800'

38 sks at 160' To Surface

KCC WICHITA

EQUIPMENT USED

NAME \_\_\_\_\_ UNIT NO. \_\_\_\_\_

NAME \_\_\_\_\_ UNIT NO. \_\_\_\_\_

Kelly Kimberlin 185

Jerry #186, Roger #193

Brad Butler  
HSI REP.

witnessed by Cliff Schenkic  
OWNER'S REP.

Shop # 48-1214033  
 Cellular # 620 437-2661  
 Office # 620 437-7582  
 Office Fax # 316 685-5908  
 Shop Address: 316-685-5926  
 3613A Y Road  
 Madison, KS 66860

Hurricane Services, Inc.  
 P.O. Box 782228  
 Wichita, KS 67278-2228

Cement, Acid or Tools  
 Service Ticket

02730

DATE 9-2-08

COUNTY Lyon CITY \_\_\_\_\_

CHARGE TO Schankie Well Serv.  
 ADDRESS P.O. Box 397 CITY Madison ST Ks. ZIP 66860-0397  
 LEASE & WELL NO. Nuessen # 4A CONTRACTOR \_\_\_\_\_  
 KIND OF JOB P.T.A. / Topoff well SEC. \_\_\_\_\_ TWP. \_\_\_\_\_ RNG. \_\_\_\_\_  
 DIR. TO LOC. \_\_\_\_\_ OLD NEW

Quantity	MATERIAL USED	Serv. Charge	
			200.00
27 SKS	60/40 Pozmix cement		234.90
50 lbs	Gel 2%		10.00
	BULK CHARGE		
m/c	BULK TRK. MILES		200.00
	PUMP TRK. MILES		N/C
1 Hr.	water Truck #193		80.00
	PLUGS		
		5.8% SALES TAX	14.20
		TOTAL	739.10

T.D. \_\_\_\_\_ CSG. SET AT \_\_\_\_\_ VOLUME \_\_\_\_\_  
 SIZE HOLE ? - possibly 7 7/8" TBG SET AT \_\_\_\_\_ VOLUME \_\_\_\_\_  
 MAX. PRESS. \_\_\_\_\_ SIZE PIPE 5 1/2"  
 PLUG DEPTH \_\_\_\_\_ PKER DEPTH \_\_\_\_\_ RECEIVED  
 PLUG USED \_\_\_\_\_ TIME FINISHED \_\_\_\_\_ NOV 17 2008

REMARKS: Well Plugged 8-28-08 > Ticket # 2710 KCC WICHITA  
Cement had fallen down inside of casing 110' from surface and down on backside  
Called on morning of 9-2-08 > fill well backup with cement on 9-2-08 6:00pm.  
Weighted Bulk Truck - used 27 SKS 60/40 Pozmix cement w/ 2% Gel  
"Thank you"

EQUIPMENT USED

NAME	UNIT NO.	NAME	UNIT NO.
<u>Kelly Kimbrelin</u>	<u>185</u>	<u>Jerry-Rodger #91, Clayton #193</u>	
<u>Brad Butler</u>		<u>Witnessed by Cliff Schankie</u>	
HSI REP.		OWNER'S REP.	

**Precision Well Perforators**  
 PO Box 401  
 Chanute, KS 66720

Date 8/25/2008  
 Invoice # 2428

**Bill To**  
 Schankie Well Service  
 Box 397  
 Madison, KS 66860

**Ship To**

P.O. #  
 Terms Net 30

Ship Date 8/25/2008  
 Due Date 9/24/2008  
 Other

Item	Description	Qty	Price	Amount
Shoot off Tubi...	Neussen #A-4 08/25/2008 Shoot off 2 3/8" Tubing at 1786.0'		450.00	450.00
Perforation	Neussen #A-5 08/25/2008 Perforate Well at 800.0'		450.00	450.00
Perforation	at 150.0' So Well can be properly plugged with cement		200.00	200.00
Perforation	<del>Neussen #A-4 08/28/2008</del> <del>Perforate Well at 800.0'</del>		450.00	450.00
Perforation	<del>at 150.0'</del> <del>So Well can be properly plugged with cement</del>		200.00	200.00

**RECEIVED**  
 NOV 17 2008  
 KCC WICHITA

Thank You!

**Precision Well Perforators**  
 luden@arcplasma.com

Subtotal \$1,750.00  
 Sales Tax (0.0%) \$0.00  
 Total \$1,750.00  
 Payments/Credits \$0.00  
 Balance Due \$1,750.00