

WELL PLUGGING RECORD

15-065-20439-00-00

Give All Information Completely
Make Required Affidavit

COUNTY Graham SEC. 23 TWP. 9S RGE. 23W E/W
Location as in quarters or footage from lines:
NW NE NW

Lease Owner Sarabell Snider Living Trust
Lease Name Nenemire 1-V Well No. _____
Office Address 4519 East English Wichita, Kansas 67218
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 4-14-83
Plugging completed 4-20-83
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

_____ Depleted
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hamel

Producing formation _____ Depth to top _____ bottom T.D. 3915'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	252'	none
				5-1/2"	3914'	2944'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped bottom with cement to 3225', shot casing @2928', 2638' and layed down a total of 90 joints of 5-1/2" casing. (2944') Plugged well with 28 gel, 1 hull, 100 cement, 12 gel, 70 cement, 50/50 pos, 6% gel, 3% cc.

Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein-contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Kansas 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of April, 1983

My Commission expires:



Irene Hoover
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
4-28-83
APR 28 1983

NOV 10 1972

WELL LOG

23-9-23W
NW NE NW

15-065-20439-00-00

COMPANY **Coal Petroleum Company**

SEC. 23 T. 9S R. 23W

FARM **J. A. Hincuire** NO. 1-7


LOC. NW NE NW

TOTAL DEPTH **3915'**

COUNTY **Graham, Kansas**

COMM. **4-27-71** COMP. **9-6-71**

CONTRACTOR **Garvey Drilling Company**



CASING

8 5/8" @ 252' w/200sx
5 1/2" @ 3914' w/175sx Top of cement 3225

ELEVATION **2337**

PRODUCTION **59 BOPD 8% wt.**

FIGURES INDICATE BOTTOM OF FORMATIONS

RECEIVED
STATE CORPORATION COMMISSION

JUN - 1 1982
67-82
CONSERVATION DIVISION
Wichita Kansas

- 252' Clay & Blue Shale
- 345' Shale
- 1376' Shale, Shale, & Sand
- 1570' Sand & Shale
- 1745' Red Bed & Shale
- 1935' Shale w/Sand Streaks
- 2151' Shale
- 2820' Shale & Lime
- 3000' Lime & Shale
- 3243' Lime
- 3915' Lime w/Shale
- 3915' RTD

Log Tops

Anhydrite	1937
Topeka	3403
Heebner	3622
Toronto	3644
Lansing	3657
B. Kansas City	3874
RTD	3915
LTD	3917

Perforated Intervals from KB

- 3828 to 3832
- 3809 to 3812
- 3726 to 3730
- 3568 to 3570
- 3528 to 3532 Last Prod. test .0 BO plus 108 BWPD

State of Kansas
County of Barton } ss

I, Charlene Marker of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the J. A. Hincuire 1-7 well.

Subscribed and sworn to before me this 11th day of May 19 71

My Commission Expires: July 6, 1974

Charlene Marker
George A. [Signature]
NOTARY PUBLIC