

15-065-20969-00-00


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Graham County, Sec. 23 Twp. 9S Rge. 23 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C E/2 E/2 NE

Lease Owner K & E Petroleum, Inc.
Lease Name Denning "A" Well No. 1
Office Address 816 Union Center, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
Dry Hole



Locate well correctly on above
Section Plat

Date Well completed Nov. 26 1977
Application for plugging filed (verbally) Nov. 26 1977
Application for plugging approved (verbally) Nov. 26 1977
Plugging commenced Nov. 26 1977
Plugging completed Nov. 26 1977
Reason for abandonment of well or producing formation
No commercial quantity of oil or gas encountered
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation Depth to top Bottom Total Depth of Well 3905'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set 1st plug at 800' with 70 sacks
2nd plug at 200' with 20 sacks
40' solid bridge with 10 sacks
Cemented with 50/50 posmix, 6% gel
Plug was down at 8:00 p.m., November 26, 1977

RECEIVED
STATE CORPORATION COMMISSION

NOV 30 1977

CONSERVATION DIVISION
Wichita, Kansas

11-30-77

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Abercrombie Drilling, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack L. Partridge, Ass't. Secretary-Treasurer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Jack L. Partridge
801 Union Center, Wichita, Kansas 67202
(Address)

29th day of November, 1977

Sandra Richman
Sandra Richman Notary Public,

SUBSCRIBED AND SWORN TO before me this

My Commission expires July 21, 1979



OPERATOR: K & E Petroleum, Inc.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Denning #1 -A
 LOCATION: C E/2 E/2 NE Section 23-9S-23W
 Graham County, Kansas
 SPUD DATE: November 18, 1977
 COMPLETION DATE: November 26, 1977

0	195	Surface clay & sand
195	1328	Shale
1328	1715	Shale & sand
1715	1942	Shale
1942	1979	Anhydrite
1979	2152	Shale
2152	2716	Shale & lime
2716	3595	Lime & shale
3595	3740	Lime
3740	3746	Lime & shale
3746	3905	Lime
	3905	Rotary Total Depth

Spud hole at 12:30 p.m., November 18, 1977. Drilled 215' of 12 1/4" hole. Ran 6 joints of 8-5/8" surface casing. Set at 214' K.B., cemented with 175 sacks common cement, 3% CaCl, 2% gel. Cement did circulate. Job was complete at 4:15 p.m., November 18, 1977.

T.D. 3905'. Set 1st plug at 800' with 70 sacks, 2nd plug at 200' with 20 sacks, 40' solid bridge with 10 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 8:00 p.m., November 26, 1977.

SAMPLE TOPS:

Anhydrite 1942' (+417)
 B/Anhydrite 1979' (+380)

RECEIVED
 STATE CORPORATION COMMISSION

NOV 30 1977

11-30-77


CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Denning #1, C E/2 E/2 NE Section 23-9S-23W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.,

BY Jack L. Partridge
 Jack L. Partridge,
 Assistant Secretary-Treasurer



Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state of this 29th day of November, 1977.

My commission expires July 21, 1979.

Sandra Richman
 Sandra Richman, Notary Public