

RECEIVED

JUN 13 2005

KCC WICHITA

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

WELL COMPLETION FORM

WELL HISTORY - DESCRIPTION OF WELL & LEASE

Form ACO-1
September 1999
Form Must Be Typed

ORIGINAL

Operator: License # 32016
Name: Pioneer Resources
Address: 177 W. Limestone Rd.
City/State/Zip: Phillipsburg, Kansas 67661
Purchaser: NCRA
Operator Contact Person: Rodger D. Wells
Phone: (785) 543-5556
Contractor: Name: Murfin Drilling Co.
License: 30606
Wellsite Geologist: Randy Kilian

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:

Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____

4-8-05 4-14-05 5-8-05
Spud Date or Date Reached TD Completion Date or
Recompletion Date Recompletion Date

API No. 15 - 065-23052-00
County: Graham
NW NE SE Sec 32 Twp 9 S. R. 21 East West
2630 feet from (S) N (circle one) Line of Section
800 feet from (E) W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE (SE) NW SW
Lease Name: De Young Well #: 1
Field Name: Cooper
Producing Formation: Arbuckle
Elevation: Ground: 2337' Kelly Bushing: 2342'
Total Depth: 3948' Plug Back Total Depth: 3940'
Amount of Surface Pipe Set and Cemented at 251 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set 1819 Feet
If Alternate II completion, cement circulated from 1809
feet depth to Surface w/ 375 sx cmt.

Drilling Fluid Management Plan Alt II NCR 8-8-08
(Data must be collected from the Reserve Pit)

Chloride content _____ ppm Fluid volume _____ bbls
Dewatering method used _____
Location of fluid disposal if hauled offsite: No fluids were removed and allowed to air dry
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Rodger D. Wells
Title: Owner Date: 6-10-05
Subscribed and sworn to before me this 10th day of June, 2005.
Notary Public: _____
Date Commission Expires: 3/3/08

NOTARY PUBLIC
STATE OF KANSAS
Douglas E. Vahia
Notary Public
State Of Kansas
My Exp. 3-3-08

KCC Office Use ONLY
No Letter of Confidentiality Attached
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

Operator Name: Pioneer Resources Lease Name: De Young Well #: 1

Sec. 32 Twp. 9 S. R. 21 East West County: Graham

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes No
(Attach Additional Sheets)

Samples Sent to Geological Survey Yes No

Cores Taken Yes No

Electric Log Run Yes No
(Submit Copy)

List All E. Logs Run:

Raditation Guard Log

Log Formation (Top), Depth and Datum Sample

| Name | Top | Datum |
|----------|------|-------|
| Anh. | 1815 | +527 |
| Base | 1850 | +492 |
| Topeka | 3318 | -976 |
| Heebner | 3524 | -1182 |
| Toronto | 3548 | -1206 |
| Lansing | 3563 | -1221 |
| BKC | 3792 | -1450 |
| Arbuckle | 3909 | -1567 |
| TD | 3948 | -1606 |

CASING RECORD New Used

Report all strings set-conductor, surface, intermediate, production, etc.

| Purpose of String | Size Hole Drilled | Size Casing Set (In O.D.) | Weight Lbs. / Ft. | Setting Depth | Type of Cement | # Sacs Used | Type and Percent Additives |
|-------------------|-------------------|---------------------------|-------------------|---------------|----------------|-------------|----------------------------|
| Surface | 12 1/4 | 8 5/8 | 7.875 | 251 | 60/40 Poz | 175 | 2%Gel 13%CC |
| Production | | 5 1/2 | 20# Ft | 3947 | ASC | 150 | ASCW 2%Gel |

ADDITIONAL CEMENTING / SQUEEZE RECORD

| Purpose: | Depth Top Bottom | Type of Cement | #Sacks Used | Type and Percent Additives |
|---|------------------|----------------|-------------|----------------------------|
| <input type="checkbox"/> Perforate <input checked="" type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone | Sur-1809 | 60/40 6% | 375 | 6% |

| Shots Per Foot | PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated | Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used) | Depth |
|----------------|---|---|-------|
| 4 | 3915-3919 | 250 Gal. Acid | 3919 |
| | | 500 Gal. 15% NE/FE | 3919 |

TUBING RECORD Size 27/8 Set At 3921 Packer At _____ Liner Run Yes No

Date of First, Resumerd Production, SWD or Enhr. May 30, 2005 Producing Method Flowing Pumping Gas Lift Other (Explain)

| Estimated Production Per 24 Hours | Oil Bbls. | Gas Mcf | Water Bbls. | Gas-Oil Ratio | Gravity |
|-----------------------------------|-----------|---------|-------------|---------------|---------|
| | 70 | 0 | 0 | 0 | 26 |

Disposition of Gas Vented Sold Used on Lease (If vented, Sumit ACO-18.)

METHOD OF COMPLETION Open Hole Perf. Dually Comp. Commingled

Production Interval Other (Specify) _____

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

Allied Cementing

ORIGINAL
SERVICE POINT
RUSSELL

| | | | | | | | |
|--|-----------------|--|-------|--------------------------------|----------------------------------|--------------------------------|--------------------------------|
| DATE <u>5/11/05</u> | SEC. | TWP. | RANGE | CALLED OUT <u>8:00 a.m.</u> | ON LOCATION <u>10:00 a.m.</u> | JOB START <u>10:15 a.m.</u> | JOB FINISH <u>1:00 p.m.</u> |
| LEASE <u>Dywig</u> | WELL # <u>1</u> | LOCATION <u>2 W of Church Road 1/2 S</u> | | | COUNTY <u>Graham</u> | STATE <u>Ks.</u> | |
| <input checked="" type="radio"/> OLD OR <input type="radio"/> NEW (Circle one) | | | | | | | |

CONTRACTOR Express
 TYPE OF JOB Port Collar
 HOLE SIZE _____ T.D. _____
 CASING SIZE 5 1/2 DEPTH _____
 TUBING SIZE 2 1/2 DEPTH _____
 DRILL PIPE _____ DEPTH _____
 TOOL Port Collar DEPTH 1810
 PRES. MAX _____ MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

EQUIPMENT

PUMP TRUCK CEMENTER Shave
 # 177 HELPER Paul
 BULK TRUCK
 # 396 DRIVER Keith
 BULK TRUCK
 # _____ DRIVER _____

REMARKS:

BD @ 3000' test @ 1200 psi
Spot 2 sand
port collar @ 1810 Open tool
broke circ. and mixed 375 sks.
displaced 9 1/2 bbl closed tool
repressured 1200 psi ran 5 jts.
reversed out washed sand off
B.P. Cement Circ

CHARGE TO: Pioneer Resources
 STREET _____
 CITY _____ STATE _____ ZIP _____

To Allied Cementing Co., Inc.

RECEIVED
 JUN 13 2005
 KCCWICHITA

OWNER _____
 CEMENT
 AMOUNT ORDERED 400 60/40 6% Gel 1/4 F.
2 sand
Used 375 sks
 COMMON 225 @ 8.70 1957.50
 POZMIX 150 @ 4.70 705.00
 GEL 19 @ 14.00 266.00
 CHLORIDE _____ @ _____
 ASC _____ @ _____
Sand 2 @ 8.50 17.00
 _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 _____ @ _____
 HANDLING 422 @ 1.60 675.20
 MILEAGE 67/52/mile 1616.44
 TOTAL 5317.14

SERVICE

DEPTH OF JOB _____
 PUMP TRUCK CHARGE 785.00
 EXTRA FOOTAGE _____ @ _____
 MILEAGE 67 @ 5.00 335.00
 MANIFOLD _____ @ _____
 _____ @ _____
 _____ @ _____
 TOTAL 1120.00

PLUG & FLOAT EQUIPMENT

_____ @ _____
 _____ @ _____
 _____ @ _____

PRINTED NA

IF PAID IN 30

ALLIED CEMENTING CO., INC. 16140

ORIGINAL ✓

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Russell

| | | | | | | | |
|---------------------------------------|----------------|----------------------------------|-----------------|--------------------------|---------------------------|-------------------------|---------------------------|
| DATE <u>4-13-05</u> | SEC. <u>32</u> | TWP. <u>9</u> | RANGE <u>21</u> | CALLED OUT <u>2:30pm</u> | ON LOCATION <u>4:30pm</u> | JOB START <u>9:45am</u> | JOB FINISH <u>10:30am</u> |
| LEASE <u>De Young</u> WELL # <u>1</u> | | LOCATION <u>CHURCH OF GOD IS</u> | | COUNTY <u>GIRARD</u> | STATE <u>Kansas</u> | | |
| OLD OR NEW (Circle one) <u>NEW</u> | | 2W 4N 4W | | | | | |

CONTRACTOR MURKIN 8
 TYPE OF JOB PRODUCTION STRING
 HOLE SIZE 7 7/8 New T.D. 3950
 CASING SIZE 5 1/2 14" DEPTH 3947'
~~TUBING SIZE~~ AFU Insert DEPTH @ 3933
 DRILL PIPE DEPTH
 TOOL Port Collar @ DEPTH 1819'
 PRES. MAX MINIMUM
 MEAS. LINE SHOE JOINT 14.0'
 CEMENT LEFT IN CSG. 14'
 PERFS.
 DISPLACEMENT 96 / BBL

OWNER
 CEMENT
 AMOUNT ORDERED 175 SK ASC 2% Gel
500 GAL WFR-2
 COMMON @
 POZMIX @
 GEL 3 @ 14.00 42.00
 CHLORIDE @
 ASC 175 @ 10.75 1881.25
 @
 @
WFR-2 500 @ 1.00 500.00
 @
 @
 @
 @
 HANDLING 178 @ 1.60 284.80
 MILEAGE 6.8 / SK / MILE 715.00
 TOTAL 3423.61

EQUIPMENT

PUMP TRUCK CEMENTER Gilean
 # 366 HELPER Shane
 BULK TRUCK
 # 213 DRIVER Craig
 BULK TRUCK
 # DRIVER

REMARKS:

Port Collar on #50 JT. (1819)
AFU INSERT (Held)
Land Plug @ 1200#
15 SK @ RAT Hole
10 SK @ Mouse Hole

THANKS

SERVICE

DEPTH OF JOB
 PUMP TRUCK CHARGE 1320.00
 EXTRA FOOTAGE @
 MILEAGE 67 @ 5.00 335.00
 @
 @
 @

RECEIVED

JUN 13 2005

TOTAL 1655.00

**KCC WICHITA WATERFORD
 PLUG & FLOAT EQUIPMENT**

Rotating Head 75.00
RED Port Collar @ 1750.00
Guide Shoe @ 160.00
AFU INSERT @ 235.00
8 Centralizers @ 55.00 440.00

CHARGE TO: Pioneer Resources
 STREET _____
 CITY _____ STATE _____ ZIP _____

ALLIED CEMENTING CO., INC. 16136

ORIGINAL ✓

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

| | | | | | | | | | | | | | | | |
|------------|--------------|--------|----|----------|------------------|-------|----|------------|--------|-------------|--------|-----------|--------|------------|--------|
| DATE | 4-8-05 | SEC. | 32 | TWP. | 9 | RANGE | 21 | CALLED OUT | 3:30pm | ON LOCATION | 5:30pm | JOB START | 6:30pm | JOB FINISH | 7:00pm |
| LEASE | De Young | WELL # | 1 | LOCATION | CHURCH OF GOD IS | | | COUNTY | Graham | STATE | KANSAS | | | | |
| OLD OR NEW | (Circle one) | | | | | | | | 2W 4N | | | | | | |

CONTRACTOR MURFIN 8

TYPE OF JOB SURFACE

HOLE SIZE 12 1/4 T.D. 251'

CASING SIZE 8 5/8 New DEPTH 251'

TUBING SIZE 2 3/8 DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG. 15'

PERFS.

DISPLACEMENT 15 / 80L

EQUIPMENT

PUMP TRUCK CEMENTER Glenn

366 HELPER Shane

BULK TRUCK

23 DRIVER GARY

BULK TRUCK

DRIVER

REMARKS:

Cement Circ.

THANKS

CHARGE TO: Pioneer Resources

STREET _____

CITY _____ STATE _____ ZIP _____

OWNER _____

CEMENT AMOUNT ORDERED 170 SK Com

2% GEL

3% CE

| | | | | |
|----------|-----------------------|---|------------------------|--------------------------|
| COMMON | <u>170</u> | @ | <u>8⁰⁰</u> | <u>1479⁰⁰</u> |
| POZMIX | | @ | | |
| GEL | <u>3</u> | @ | <u>14⁰⁰</u> | <u>42⁰⁰</u> |
| CHLORIDE | <u>5</u> | @ | <u>38⁰⁰</u> | <u>190⁰⁰</u> |
| ASC | | @ | | |
| | | @ | | |
| | | @ | | |
| | | @ | | |
| | | @ | | |
| | | @ | | |
| | | @ | | |
| | | @ | | |
| | | @ | | |
| HANDLING | <u>178</u> | @ | <u>16⁰⁰</u> | <u>284⁰⁰</u> |
| MILEAGE | <u>66 / SK / MILE</u> | | | <u>704⁰⁰</u> |
| TOTAL | | | | <u>2700⁶⁸</u> |

SERVICE

DEPTH OF JOB _____

PUMP TRUCK CHARGE 670⁰⁰

EXTRA FOOTAGE @ _____

MILEAGE 66 @ 5⁰⁰ 330⁰⁰

RECEIVED

JUN 13 2005

TOTAL 1000⁰⁰

KCC WICHITA

PLUG & FLOAT EQUIPMENT

MANIFOLD @ _____

@ _____

@ _____

@ _____

@ _____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment