

*2*  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-179-20207-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 27 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
05-27-1969

Operator's Full Name W. A. Herman, et al,  
Complete Address Box #797, Great Bend, Kansas.  
Lease Name Zerr Well No. 1  
Location Appr. - SW-SW, Sec. 22 Twp. 10 Rge. (E) (W) 27  
County Sheridan Total Depth 4030'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated       
Plugging Contractor Chief Drilling Company, Incorporated,  
Address Box #797, Great Bend, Kansas. License No.       
Operation Completed: Hour 8:30 PM Day 21 Month 5 Year 1969

The above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 165 Sx.  
Top of Dakota section @ 960'.  
Circulated hole with heavy mud. Pulled DP to 1185' and displaced 100 Sx. cement thru  
DP from 1185' to 860'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from  
215' to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 5/27/69  
INV. NO. 9834-11

Signed: M. L. Nichols  
Well Plugging Supervisor