

KANSAS

94
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 7 1971
CONSERVATION DIVISION
Wichita, Kansas
05-07-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20279-00-00

Operator's Full Name W. A. Herman, et al,

Complete Address 416 West 16th Street, Hays, Kansas.

Lease Name Kraft Well No. 1

Location CSE-NW Sec. 22 Twp. 10 Rge. (E) (W)27

County Sheridan Total Depth 4050'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 9:00 AM Day 2 Month 5 Year 1971

The above well was plugged as follows:

206'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 950'.

Circulated hole with heavy mud. Pulled DP to 1175' and displaced 100 Sx. cement thru
DP from 1175' to 850'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from
215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *A. L. Nichols*
Well Plugging Supervisor

DATE 5/13/71

INV. NO. 3681-W