

KANSAS

Y STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
APR 20 1973
04-20-1973
CONSERVATION DIVISION
Wichita, Kansas

15-177 20335-00-00

Operator's Full Name Dreiling Oil, Incorporated,
Complete Address R. R. #2, Victoria, Kansas.
Lease Name Zerr Well No. 1
Location CS/2-SW Sec. 22 Twp. 10 Rge. (E) (W) 27
County Sheridan Total Depth 3851'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 11:45 AM Day 17 Month 4 Year 1973

The above well was plugged as follows:

204'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 950'. (This Well Temporarily Abandoned 12/1/72).
Squeezed well initially with 5 sacks hulls and 11 sacks gel and followed with 110
Cu. Ft. cement from 1175' to 850' then 16 sacks gel from 850' to 210' and followed
with 30 Cu. Ft. cement from 210' to 135' then 3 sacks gel from 135' to 25' and fin-
ally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in pressure-500#.
Final shut-in pressure-200#. (Mudding and Cementing by Sun Oil Well Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Nichols*
Well Plugging Supervisor

DATE 4/23/73
INV. NO. 9268-W