

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 20 1973

CONSERVATION DIVISION
Wichita, Kansas

04-20-1973

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-179-20207-00-01

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Zerr Well No. 2

Location CSW-SW Sec. 22 Twp. 10 Rge. (E) (W) 27

County Sheridan Total Depth 4030'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 1:30 Pm Day 17 Month 4 Year 1973

The above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 160 Sx. (WASHDOWN).
4028'--4 1/2" Casing cemented on bottom with 225 Sx. Top of perforations @ 3796'.

Sanded well back to 3500' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing
(2500') and squeezed well initially with 5 sacks hulls and 11 sacks gel and followed
with 110 Cu. Ft. cement from 1175' to 850' then 16 sacks gel from 850' to 210' and
followed with 30 Cu. Ft. cement from 210' to 135' then 3 sacks gel from 135' to 25'
and finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in pressure
-300#. Final shut-in pressure-100#. (Mudding and cementing by Sun Oil Well Cementing,
Inc.).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 4/23/73
INV. NO. 7269-4