

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20284-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUN 1 1971
CONSERVATION DIVISION
Wichita, Kansas
06-01-1971

Operator's Full Name Dreiling Oil, Incorporated,
Complete Address R. R. #2, Victoria, Kansas.
Lease Name Gugler Well No. 1
Location SW-NE Sec. 28 Twp. 10 Rge. (E) (W) 27
County Sheridan Total Depth 4115'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above

Address License No.
Operation Completed: Hour 3:00 PM Day 27 Month 5 Year 1971

The above well was plugged as follows:

208'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. -Pulled DP- to 1225' and displaced 100 Sx. cement thru
DP from 1225' to 900'. Pulled DP to 215' and displaced 25 Sx. cement thru DP from 215'
to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. J. J. J.
Well Plugging Supervisor

DATE 6/1/71
INV. NO. 3789-11