

R
KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

JUN 19 1972
06-19-1972
CONSERVATION DIVISION
Wichita, Kansas

15-179-20312-00-00

Operator's Full Name Dreiling Oil, Incorporated,
Complete Address R. R. #2, Victoria, Kansas.
Lease Name Arnhold Well No. 1
Location CSW-NE Sec. 27 Twp. 10 Rge. (E) (W) 27
County Sheridan Total Depth 3909'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Above
Address License No.
Operation Completed: Hour 1:15 AM Day 17 Month 6 Year 1972

The above well was plugged as follows:

258'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1075'.
Circulated hole with heavy mud. Pulled DP to 1300' and displaced 110 Cu. Ft. cement
thru DP from 1300' to 975'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Fields
Well Plugging Supervisor

INVOICED

DATE 6/20/72
INV. NO. 5896-W