

KANSAS

Form CP-3
Rev. 6-9-67

af
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20086-00-00

RECEIVED
STATE CORPORATION COMMISSION
APR 8 1968
CONSERVATION DIVISION
Wichita, Kansas
04-08-1968

Operator's Full Name Abercrombie Drilling, Incorporated,

Complete Address 801 Union Center Building, Wichita, Kansas.

Lease Name Heier Well No. 1

Location CNW-NE Sec. 1 Twp. 10 Rge. (E) (W)29

County Sheridan Total Depth 4235

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 5:00 PM Day 3 Month 4 Year 1968

The above well was plugged as follows:

226'--7 7/8" OD Surface pipe, cement circulated with 125 Sx. (6 3/4" Hole)
Top of Dakota section @ 1220'.

Circulated hole with heavy mud. Pulled DP to 1450' and displaced 80 Sx. cement thru
DP from 1450' to 1125'. Pulled DP to 240' and displaced 15 Sx. cement thru DP from
240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar. (Cementing operations performed by Sun Oil Well Cementing, Inc.)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Nichols*
Well Plugging Supervisor

DATE 4/8/68
INV. NO. 1540-W