

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1969
CONSERVATION DIVISION
Wichita, Kansas
10-14-1969

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20235-00-00

Operator's Full Name Braden Drilling Company,

Complete Address 1620 Wichita Plaza Building, Wichita, Kansas.

Lease Name Blank Well No. 2

Location CSW-NE Sec. 15 Twp. 10 Rge. (E) (W) 29

County Sheridan Total Depth 4200'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Sage Drilling Company, Incorporated,

Address 500 Bitting Building, Wichita, Ks. License No.

Operation Completed: Hour 1:30 PM Day 11 Month 10 Year 1969

The above well was plugged as follows:

289'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1200'.

Circulated hole with heavy mud. Pulled DP to 1425' and displaced 100 Sx. cement thru
DP from 1425' to 1100'. Pulled DP to 310' and displaced 20 Sx. cement thru DP from
310' to 250'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 10-14-69

INV. NO. 649-W