

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1970
CONSERVATION DIVISION
Wichita, Kansas

01-15-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20148-00-00

Operator's Full Name Braden Drilling, Incorporated.

Complete Address 1620 Wichita Plaza Building, Wichita, Kansas.

Lease Name Blank Well No. 1

Location NE-NE Sec. 15 Twp. 10 Rge. (E) (W) 29

County Sheridan Total Depth 4238'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling Company, Incorporated,

Address Box #221, Great Bend, Kansas. License No. 637

Operation Completed: Hour 11:00 AM Day 10 Month 1 Year 1970

The above well was plugged as follows:

288'--8 5/8" Surface casing, cement circulated.

4230'--5 1/2" Production casing cemented on bottom with Temperature Survey showing top of cement @ 3516'. Well Plugged back to 3990'. Top perforations @ 3949'.

Sanded well back-to-3525' and set 5 Sx. cement with-dump bailer.- Pulled 5 1/2" casing

and squeezed well initially with 5 sacks hulls and 10 Sacks gel and followed with

100 Sx. cement from 1125' to 1100' then 20 sacks gel from 1100' to 300' and followed

with 25 Sx. cement from 300' to 225' then 5 sacks gel from 225' to 30' and finally

10 Sx. cement to bottom of cellar. Maximum pump-in pressure-250#. Final shut-in

pressure-100#. (Mudding and cement operations by Allied Cementing).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 1/15/90

INV. NO. 1258-W