

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-179-20374-00-00

RECEIVED
STATE CORPORATION COMMISSION
03-11-1974
MAR 11 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name F & M Oil Company, Incorporated,

Complete Address 603 Union Center, Wichita, Kansas.

Lease Name Hecht Well No. 1

Location CNW-SE Sec. 15 Twp. 10 Rge. (E) (W) 30

County Sheridan Total Depth 4570

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas License No.

Operation Completed: Hour 8:30 PM Day 3 Month 7 Year 1974

The above well was plugged as follows:

298'--8 5/8" surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1275'.

Circulated hole with heavy mud. Pulled DP to 1500' and displaced 110 Cu. Ft. cement
thru DP from 1500' to 1175'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3/12/74
INV. NO. 8711-W

Signed: H. L. D. [Signature]
Well Plugging Supervisor