

15-163 - 20164-00-00

Form CP-3
Rev. 6-26-62



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 26 1968
CONSERVATION DIVISION
Wichita, Kansas
12-26-68

Operator's Full Name Three G Oil, Inc.

Complete Address: 1101 Wichita Plaza Wichita, Kansas

Lease Name Baumgarten Well No. 1

Location NW NW SW Sec. 25 Twp. 9 Rge. 19 (E) (W)XX

County Rooks Total Depth 3670

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated: _____

Plugging Contractor: Dunne-Gardner

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 5P Day 23 Month 12 Year 1968

The Above well was plugged as follows:

RTD 3670' 8 5/8 csg set at 220' cwc Cmt. Mat. 50-50 poz cmt. W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sc cmt. thru drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Rio J. Massey
Well Plugging Supervisor

DATE 12-26-68

INV. NO. 9109-W