

15-163-19388-00-00

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE-NE NE

SEC. 25 TWP. 9 RGE. 19W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease ~~Baumgartner~~ Baumgartner

Operator Harbor Drilling Co Address Box #24 - Wichita - Kansas

Field _____ County Boone

Total Depth 3657 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 254 ft Circulated with Cement
5 1/2" casing set at 3633 ft & cemented with 100 sacks cement
Filled hole back from bottom to 3630 ft & put in
10 sacks of cement with Mump Bally. Shot off &
recovered 2930 ft of 5 1/2" casing. Filled hole with mud
& 250 ft - Plug & 20 sacks of cement at 250 ft - Surface
Plug 20 ft below the surface & 10 sacks of cement.
Mud between plugs.

Frank Carroll
Pipe Puller & Pluggers

C. M. Stough
District Conservation Agent

Date 10-16-49

10-20-47

PLUGGING
FILE SEC 25 T 9 R 19W
BOOK PAGE 141 LINE 8