

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 16 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Dean Ulrich of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Ulrich guarantees payment of the plugging fee.

Operator's full Name: Dale Reese,

Complete Address: 415 East Prescott, Salina, Kansas.

Lease Name: Bittel Well No. 1

Location: SE-SW-SE Sec. 11 Twp. 10 Rge. (E)(W) 26

County: Sheridan Total Depth 4050' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Ulrich was instructed to plug the well as follows:

234'--8 5/8" Surface casing, cement circulated with 160 Sx.  
Top of Dakota section @ 1025'.

Circulate hole with heavy mud. Pull DP to 1250' and displace 110 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

*H. L. Nichols*  
Conservation Division Agent