

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Millard Lindsey of Cities Service Oil Company, has this date requested permission to plug the following described well:

Mr. Lindsey guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company,

Complete Address: Box #553, Russell, Kansas.

Lease Name: Evergreen NW LKC Unit Well No.

Location: SE-NW-SE Sec. 17 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth 3925' RTD Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lindsey was instructed to plug the well as follows:

185'--8 5/8" Surface casing, cement circulated with 150 Sx.
3825'--5 1/2" Production casing cemented on bottom with 125 Sx. Well plugged back to 3903'. hole full of fiber glass tubing and junk to 1296'.

Squeeze well with 5 sacks bulls, 30 sacks gel and 130 Sx. cement, staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent