



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 31 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Ray Blandin of Cities Service Oil Company. has this date requested permission to plug the following described well:

Mr. Blandin guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company.

Complete Address: Box #553, Russell, Kansas.

Lease Name: Evergreen NW KC Unit Well No. 114-W

Location: NW-SE-NW Sec. 17 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth 3860 Oil Well X

Gas Well Input Well X ^{FT} ^{KCC} SWD Well D & A Lost Hole

Mr. Blandin was instructed to plug the well as follows:

220'--8 5/8" Surface casing, cement circulated with 150 Sx.
3858'--5 1/2" casing cemented on bottom with 125 Sx. Well plugged back to 3836'. Top perforations from 3681' to 3684'.

Run tubing to bottom and displace 25 Sx. cement thru tubing. Pull tubing to 3625' and circulate heavy gel mud using 25 sacks gel. Pull tubing to 1275' and displace 60 Sx. cement thru tubing. Pull tubing to 240' and displace 10 Sx. cement. Pull tubing, fill 5 1/2" to bottom of cellar with 5 Sx. cement.

Very truly yours,

A. L. Nichols
 Conservation Division Agent