

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

FEB 26 1973

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Sunflower Operating Company,

Complete Address: Box #422, Eldorado, Kansas.

Lease Name: Robinson Well No. A-4

Location: SE-SE-NW Sec. 17 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth 3907' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Unruh was instructed to plug the well as follows:

183'--8 5/8" Surface casing, cement circulated with 150 Sx.  
3906'--5 1/2" Production casing cemented on bottom with 100 Sx. Well  
plugged back to 3902'. Top perforations from 3722' to 3724'.

Sand well back to 3700' and set 5 Sx. cement with dump bailer. Pull 5 1/2"  
casing and squeeze well with 5 sacks hulls, 25 sacks gel and 150 Cu. Ft.  
cement, staged.

Very truly yours, CP-2

M. L. Nichols  
Conservation Division Agent