

15-179-20238-0000

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 2 1969  
CONSERVATION DIVISION  
Wichita, Kansas

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Fred Damme of Red Tiger Drilling Company, has this date requested permission to plug the following described well:

Mr. Damme guarantees payment of the plugging fee.

Operator's full Name: Koch Exploration Company

Complete Address: Box #2256, Wichita, Kansas

Lease Name: Werth Well No. 1

Location: SE-NE Sec. 15 Twp. 10 Rge. (E)(W) 26

County: Sheridan Total Depth 4120 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Damme was instructed to plug the well as follows:

218'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1050'.

Circulate hole with heavy mud. Pull DP to 1275' and displace 100 Sx.  
cement thru DP. Pull DP to 250' and displace 25 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

M. L. Dehels  
Conservation Division Agent