



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 26 1973

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Sunflower Operating Company,

Complete Address: Box #422, Eldorado, Kansas.

Lease Name: Robinson Well No. A-11

Location: SE-SE-NE Sec. 17 Twp. 9 Rge. (E)(W) 23

County: Graham Total Depth 3965 Oil Well

Gas Well Input Well X SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

210'--8 5/8" Surface casing, cement circulated with 175 Sx.
3965'--5 1/2" Production casing cemented on bottom with 150 Sx. Well
plugged back to 3935'. Top perforations from 3784' to 3787'.

Sand well back to 3700' and set 5 Sx. cement with dump bailer. Pull 5 1/2"
casing and squeeze well with 5 sacks hulls, 25 sacks gel and 150 Cu. Ft.
cement, staged.

Very truly yours,


Conservation Division Agent