



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 9 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jerb Ogle of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Ogle guarantees payment of the plugging fee.

Operator's full Name: Hinkle Oil Company,

Complete Address: 1016 Union Center, Wichita, Kansas.

Lease Name: McWilliams Well No. 1

Location: NW-NE-NW Sec. 23 Twp. 10 Rge. (E)(W) 26

County: Sheridan Total Depth 4085' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ogle was instructed to plug the well as follows:

257'--8 5/8" Surface casing, cement circulated with 180 Sx.
Top of Dakota section @ 1050'.

Circulate hole with heavy mud. Pull DP to 1275' and displace 110 Cu. Ft. cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

K. L. Dehile
Conservation Division Agent