

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 11 1967

12-11-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Norman Cook of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling, Inc., & McClure Oil Co.

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name: Zerr Well No. 1

Location: SW-SE-NW Sec. 4 Twp. 10 Rge. (E)(W) 27

County Sheridan Total Depth 4084 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

190'--7 5/8" Surface pipe, cement circulated with 135 Sx. (6 1/2" Hole).
Dakota section from 890' to 1070'.

Circulate hole with heavy mud. Pull DP to 1090' and displace 65 Sx.
cement thru DP. Pull DP to 210' and displace 15 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 5 Sx. cement to
bottom of cellar.

Very truly yours,

Conservation Division Agent