

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 6 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ronnie Parks of Gabbert-Jones, Incorporated has this date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: Rosen Oil Corporation.

Complete Address: 200 Sutton Place, Wichita, Kansas.

Lease Name: Zerr Well No. 1

Location: SE-NE-SW Sec. 11 Twp. 10 Rge. (E)(W) 27

County: Sheridan Total Depth 4100' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Parks was instructed to plug the well as follows:

220'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1050'.

Circulate hole with heavy mud. Pull DP to 1300' and displace 110 Cu. Ft.
Cement thru DP. Pull DP to 245' and displace 30 Cu Ft. cement thru DP
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. to bottom of
cellar.

Very truly yours,

A. L. Pichek
Conservation Division Agent