

15-179-20956-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-179-20,956 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Rine Exploration Company OPERATOR'S LICENSE NO. 5020

ADDRESS 300 W. Douglas, Suite 645, Wichita, KS 67202-2904 PHONE # (316) 262-5418

LEASE (FARM) Johnson WELL NO. 2-17 WELL LOCATION C S/2 NW COUNTY Sheridan

SEC. 17 TWP. 10S RGE. 26 (~~E) (W)~~ TOTAL DEPTH 4175' PLUG BACK TD _____

Check One:

OIL WELL _____ GAS WELL _____ D & A x SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 319' CEMENTED WITH 200 SACKS

CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

PERFORATED AT _____

CONDITION OF WELL: GOOD x POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING Circulate heavy mud in hole. 1st plug at 2300'-20 sx. 2nd plug at 1355'-100 sx. and 1 sk. Flocel. 3rd plug at 360'-40 sx. 4th plug at 40'-10 sx.

w/wiper plug. Rathole-15 sx. All cement 60/40 pozmix, 6% gel.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? No
(If not explain.) Sent to operator for completion.

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at 1:00 a.m. on 02-28-90

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley PHONE # (913) 674-5768

ADDRESS 216 E. McFarland, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

MAD 27 1990
3-27-90
CONSERVATION DIVISION
Wichita, Kansas

SIGNED: Jack R. Wharton
(Operator or Agent)

DATE: March 26, 1990