

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

RECEIVED  
STATE CORPORATION COMMISSION

NOV 15 1988

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER 15-179-20,932-00-00 (of this well) CONSERVATION DIVISION  
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR K & E Petroleum, Inc. OPERATORS LICENSE NO. 5267

ADDRESS 100 S. Main, Suite 300, Wichita, KS 67202 PHONE # (316) 264-4301

LEASE (FARM) Miller "B" WELL NO. 1 WELL LOCATION C E/2 E/2 NE COUNTY Sheridan

SEC. 18 TWP. 10S RGE. 26 ~~(E) (W)~~ TOTAL DEPTH 4140' PLUG BACK TO \_\_\_\_\_

Check One:

OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ D & A XX SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 8 5/8" SET AT 272' CEMENTED WITH 190 SACKS

CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

PERFORATED AT \_\_\_\_\_

CONDITION OF WELL: GOOD XX POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 1st plug 2270'-25 sx. 2nd plug 1350'-100

sx. 3rd plug 320'-40 sx. 4th plug 40' solid bridge, wiper plug-10 sx. Rathole-15 sx. All

cement 60/40 posmix, 6% gel, 2 sx cello flake.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACC-1 FILED? No  
(If not, explain) Sent to operator for completion

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at 8:00 a.m. on 11-08-88

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Harold Maley PHONE # (913) 674-5768

ADDRESS 216 E. McFarland, Hill City, KS 67642

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 801 Union Center, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Jack H. Wharton  
(Operator or Agent)

DATE 11-11-88