

4- 031699

6-8-92

91 R

15-065-20189-00-00

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: ~~15-065-~~ 1969

NW NW NE /4 SEC. 11, 10 S, 24 W  
4950 feet from S section line  
2310 feet from E section line

Operator license# 4767

Lease Elmo Gano well #"P"1

Operator: Ritchie Exploration, Inc.

County Graham

133.25

Address: 125 N. Market  
#1000  
Wichita, Kansas 67202

Well total depth 4100 feet PBDT 4065'  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 185 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

Plugging contractor: Kelso Casing Pulling License# 6050

Address: Chase, Kansas

Company to plug at: Hour: P.M. Day: 8 Month: June Year: 92

Plugging proposal received from: Monte

Company: Kelso Casing Pulling

Phone:                      RECEIVED

Were: Order 250 sx. 65/35 pozmix - 10% gel. - 500# hulls.  
Allied Cement Company. Hole open to perf's.

KANSAS CORPORATION COMMISSION

JUL 2 1992

07-02-1992

CONSERVATION DIVISION  
WICHITA, KS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[ X ], Part[      ], None[      ]

Completed: Hour: 1:00P.M., Day: 8, Month: June, Year: 92

Actual plugging report: 8 5/8" set @ 185' w/150 sx. 4 1/2" set @ 4099'  
w/200 sx. Perf. 3824' - 3998'. Shots @ 1925' and 1300'. Recovered  
1300' of 4 1/2". Mix and pump cement blend slurry to bottom down 4 1/2".  
Pulled 700' of 4 1/2" to 600'. Mix and pump 125 sx. of hulls.  
Circulated cement. Laid down 4 1/2". Capped well with 25 sx. Used  
total 250 sx. cement blend with 500# hulls mixed in. Plug complete.

Remarks:

Condition of casing(in hole):GOOD X BAD      Anhy.plug:YES X NO       
Bottom plug(in place):YES X, CALC     , NO      Dakota plug:YES X, NO       
Plugged through TUBING     , CASING X. Elevation:      GL     

I did [ X ] / did not [      ] observe the plugging.

Carl Goodrow

DATE 7-8-92

HD

(agent)

INV. NO. 35638