

1-12-15-065-20443-00-00 28 29 R

6 031321

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-1971  
E/2 NE SE 21 10 25  
SEC. \_\_\_\_\_, T \_\_\_\_\_, S, R \_\_\_\_\_ W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Operator: Beren Corp  
Name & Address: Box 723  
Hays, Ks. 67601

3300 feet from S section line  
4620 feet from E section line

Lease Name Bollig Well # 1  
County Graham 132.93

Well Total Depth 4090 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 190 sks

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor B. J. Titan  
Address Hays, Ks. License Number \_\_\_\_\_

Company to plug at: Hour: PM Day: 12 Month: Jan Year: 19 90

Plugging proposal received from George

(company name) Beren (phone) \_\_\_\_\_

were: 8 5/8" set at 190' w/175 sks. 5 1/2" casing set at 4087 w/125 sks.  
Order 350 sks 65/35 poz 10% gel 2% dicel, 500# hulls. B. J. Titan  
Wellbrock water trucks. Okmar rig. Shots at 1330' and 2050 anhy.

Plugging Proposal Received by Carl  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 6:11 PM Day: 12 Month: Jan Year: 19 90

ACTUAL PLUGGING REPORT

Ran tubing to 4000'. Pump 100 sks cement blend, Lay down  
2000' of tubing. Pump 75 sks lay down 1400' of tubing to 600'. Pump 25 sks cement  
blend to surface. Hook up to annulus mix and pump 100 sks cement blend to max psi  
300#. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 26 1990  
01-26-1990  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

I (did ~~not~~) observe this plugging.

INVOICED  
DATE FEB 05 1990  
INV. NO. 27312

*Gil S*

Signed Carl Goodrow  
(TECHNICIAN)  
Carl Goodrow